



Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number 12875899
Procuring Entity MUNICIPALITY OF TIAONG, QUEZON
Title Construction of BFP Building
Area of Delivery Quezon

Solicitation Number: I-2026-03-01	Status	Active
Trade Agreement: Implementing Rules and Regulations	Associated Components	4
Procurement Mode: Public Bidding	Bid Supplements	0
Classification: Civil Works	Document Request List	0
Category: Construction Projects	Date Published	25/03/2026
Approved Budget for the Contract: PHP 6,790,586.46	Last Updated / Time	25/03/2026 00:00 AM
Delivery Period: 150 Day/s	Closing Date / Time	13/04/2026 14:00 PM
Client Agency:		
Contact Person: Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851 noreenaortega@gmail.com		

Description

B.5 Project Billboard/Signboard
Quantity: 1.00 each

Materials

Ordinary Plywood (1/2" x 4' x 8') 2.00 pcs.
 Coco Lumber (2" x 3" x 12') 5.00 pcs.
 Tarpaulin (8' x 8') 1.00 unit
 Assorted CWN 1.00 kg.

Labor

1 Carpenter 0.50 day
 2 Laborer 0.50 day

B.7 Construction Safety and Health
Quantity: 1.00 lot

Materials

Safety Helmet 16.00 pcs
 Hand Gloves 16.00 pairs
 Safety Shoes 16.00 pairs
 Misc (Medicine, Medicine Cabinet, Water, First Aid Kit) 1.00 lot

Labor

1 Safety Officer 15.00 days

1 First Aide 15.00 days

SPL-1 Demolition
Quantity: 1.00 l.s.

Labor
1 Foreman 4.00 days
2 Skilled Laborer 4.00 days
3 Laborer 4.00 days

Equipment
1 Backhoe (0.80 cu.m) 12.00 hour
1 Dump Truck (12 cu.yd) 12.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

803(1)a Structure Excavation, Common Soil
Quantity: 57.30 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment
1 Backhoe (0.80 cu.m) 3.00 hour
2 Dump Truck (12 cu.yd) 3.00 hour

804(1)a Embankment from Structure Excavation
Quantity: 45.00 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment
1 Backhoe (0.80 cu.m) 6.00 hour
1 Plate Compactor 6.00 hour

804(2)a Embankment from Borrow
Quantity: 28.37 cu.m

Materials
Common Borrow 36.00 cu.m

Labor
1 Foreman 1.00 day
3 Laborer 1.00 day

Equipment
1 Backhoe (0.80 cu.m) 3.00 hour
1 Plate Compactor 3.00 hour

804(7) Gravel Fill
Quantity 7.35 cu.m

Materials
Gravel Fill 8.00 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment
1 Plate Compactor 6.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

900(1)c Structural Concrete (3000 psi, Class A, 28 days)
Quantity 13.00 cu.m

Materials
Ready Mix Concrete 3000Psi @ 28 Days 14.30 cu.m

Labor
1 Foreman 3.00 days
2 Skilled Laborer 3.00 days
6 Laborer 3.00 days

Equipment

2 Concrete Vibrator 4.00 hour
1 Pumpcrete 5.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

900(1)d Structural Concrete (4000 psi, Class A, 28 days)
Quantity 63.20 cu.m

Materials

Ready Mix Concrete 4000Psi @ 28 Days 70.00 cu.m

Labor

1 Foreman 6.00 days
2 Skilled Laborer 6.00 days
6 Laborer 6.00 days

Equipment

2 Concrete Vibrator 19.00 hour
1 Pumpcrete 12.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

902(1)a1 Reinforcing Steel (Deformed) Grade 40
Quantity 5,212.70 kg

Materials

Reinforcing Steel Bars Deformed Grade 40 5,473.00 kg
GI Tie Wire #16 83.00 kg

Labor

1 Foreman 7.00 days
3 Skilled Laborer 7.00 days
8 Laborer 7.00 days

Equipment

1 Bar Cutter 20.00 hour
1 Bar Bender 20.00 hour
Minor Tools (10% of Labor Cost) 1.00 lot

902(1)a2 Reinforcing Steel (Deformed) Grade 60
Quantity 9,821.20 kg

Materials

Reinforcing Steel Bars Deformed Grade 60 9,822.00 kg
GI Tie Wire #16 147.33 kg

Labor

1 Foreman 12.00 days
3 Skilled Laborer 12.00 days
8 Laborer 12.00 days

Equipment

1 Bar Cutter 38.00 hour
1 Bar Bender 38.00 hour
Minor Tools (10% of Labor Cost) 1.00 lot

903(2) Formworks and Falseworks
Quantity 461.00 sq.m

Materials

Phenolic Board - 1.22m x 2.44m x 18mm 40.00 pc
Good Lumber 1,090.00 bd.ft
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 13.00 days
4 Skilled Laborer 13.00 days
6 Laborer 13.00 days

Stripping

1 Foreman 7.00 days
6 Laborer 7.00 days

Equipment

40 H-Frame 1.7 m x 1.2m, set 32.00 hrs
2pcs H-frames
4pcs diagonal cross braces
4pcs Horizontal cross braces
8pcs joint pins
62 Shoring Jack,3.8 m full extension 32.00 hrs
80 Adj. U-Head Jack, 0.60m 32.00 hrs
80 Adj. Base Jack, 0.60m 32.00 hrs
62 1-1/2" GI Pipe x 6.0 m 32.00 hrs
16 1-1/2" GI Pipe x 3.0 m 32.00 hrs
32 1-1/2" GI Pipe x 4.0 m 32.00 hrs
216 1-1/2" GI Pipe x 1.0 m 32.00 hrs
278 Tie Rod x 0.60m 32.00 hrs
558 Round Wing Not 32.00 hrs

1000(1) Soil Poisoning
Quantity 10.00 liter

Materials
Soil Poisoning 10.00 lit

Labor
1 Foreman 2.00 day
1 Laborer 2.00 day

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1046(2)a2 CHB Non-Load Bearing (including Reinforcing Steel), 150mm
Quantity 285.36 sq.m

Materials
CHB Ordinary (150mm x 230mm x 406mm) 3,710.00 pcs
Portland Cement 152.00 bag
Sand 12.00 cu.m
Reinforcing Steel Bars Deformed Grade 40 1,025.00 kg
GI Tie Wire #16 15.00 kg
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 12.00 days
2 Skilled Laborer 12.00 days
3 Laborer 12.00 days

Equipment
1 One Bagger Mixer 90.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1003(2) Drywall
Quantity 50.90 sq.m

Materials
Fiber Cement Board 6mm thk 38.00 pcs
Metal Studs 0.6mm thk. 3m 61.00 pcs
Rivets 5,956.00 pcs
1" Metal Screw 204.00 pcs
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 7.00 days
2 Skilled Laborer 7.00 days
3 Laborer 7.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1010(2)a Doors, Flush
Quantity 16.59 sq.m.

Materials
Flush Hollow Core Door with Door Jamb 9.45 sq.m
PVC Swing Door with Door Jamb 7.14 sq.m
Door Locks (Schlage or Equivalent) 10.00 set

Door Hinge (50mm x 101mm) 40.00 pc
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 3.00 days
1 Skilled Laborer 3.00 days
1 Laborer 3.00 days

1010(2)c Doors (Glass Panel)
Quantity 5.46 sq.m

Materials

Glass Door Panel 5.46 sq.m
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
1 Laborer 1.00 days

1008(1)c Aluminum Glass Window
Quantity 28.85 sq.m

Materials

Aluminum framed Glass Window 28.85 sq.m
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 6.00 days
1 Skilled Laborer 6.00 days
1 Laborer 6.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1027(1) Cement Plaster Finish
Quantity 720.52 sq.m

Materials

Portland Cement 238.00 bag
Sand 20.00 cu.m

Labor

1 Foreman 13.00 days
2 Skilled Laborer 13.00 days
4 Laborer 13.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1003(1)a1 Ceiling (4.5mm, Metal Frame, Fiber Cement Board)
Quantity 184.00 sq.m

Materials

15mm thick Armstrong acoustic ceiling/Fiber cement board 68.00 pcs
Metal Furring 3m length 209.00 pcs
Carrying Channels 66.00 pcs
Hanger Bars/Rod 28.00 pcs
Channel clip 1,104.00 pcs
Wall Angle 77.00 pcs
Rivets 2,576.00 pcs
1" Metal Screw 736.00 pcs

Labor

1 Foreman 19.00 days
1 Skilled Laborer 19.00 days
2 Laborer 19.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1038(1) Reflective Insulation
Quantity 109.00 sq.m

Materials

Reflective Insulation, 10 mm thk 109.00 sq.m
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 2.00 days
1 Skilled Laborer 2.00 days
2 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1018(1) Tile Works

Quantity 169.10 sq.m

Materials

60cm x 60 cm Tiles 455.00 pcs
30cm x 30 cm Tiles 537.00 pcs
Cement 82.00 bags
Sand 7.00 cu.m
Tile Adhesive 5.00 bags
Tile Grout 53.00 bags
Consumables (5% of Material Cost) 1.00 lot

Labor

1 Foreman 16.00 days
5 Skilled Laborer 16.00 days
5 Laborer 16.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1032 Painting Works

Quantity 672.40 sq.m

Materials

Concrete Neutralizer 14.00 gal
Concrete Sealer/Primer 27.00 gal
Patching Compound 44.00 gal
Semi-Gloss Latex (2 coats only) 64.00 gal
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 25.00 days
2 Skilled Laborer 25.00 days
1 Laborer 25.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1032(1)c Painting Works (Steel)

Quantity 203.20 sq.m

Materials

Red Oxide Primer 10.00 gal
Flat Wall Enamel 22.00 gal
Paint Thinner 51.00 liter
Tinting Color 3.00 liter
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 7.00 days
2 Skilled Laborer 7.00 days
1 Laborer 7.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1014(1)b2 Prepainted Metal Sheets (above 0.427mm) Rib Type Long Span

Quantity 104.00 sq.m.

Materials

Long Span Rib Type Colored Roof, Ga. 26 110.00 sq.m.

Tekscrew 1,040.00 pcs
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 7.00 days
2 Skilled Laborer 7.00 days
2 Laborer 7.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(7) Structural Steel (TRUSS)

Quantity 2,870.00 kg

Materials

Structural Steel Truss 2,870.00 kg
Acetylene 32.00 kg
Oxygen 64.00 kg
Welding Rod 58.00 kg
Consumables Materials (1% of Matl. Cost) 1.00 lot

Labor

1 Foreman 7.00 days
2 Skilled Laborer 7.00 days
2 Laborer 7.00 days

Erection

2 Skilled Laborer 4.00 days
3 Laborer 4.00 days

Equipment

1 Welding Machine, Electric Driven/DC Output, 500 Amp 26.00 hours
1 Cutting Outfit 9.00 hours
1 Grinding Machine and Accessories 28.00 hours
1 Cargo/Service Truck, 2-5 mt, 160 hp 4.00 hours
1 Boom Truck, NXG1160D3ZAL1X, 197 hp 6.00 hours
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(8)b Structural Steel (Purlins)

Quantity 432.00 kg

Materials

Structural Steel Purlins 432.00 kg
Welding Rod 9.00 kg
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 4.00 days
2 Skilled Laborer 4.00 days
4 Laborer 4.00 days

Equipment

2 Welding Machine, Electric Driven/DC Output, 500 Amp 12.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(5) Metal Structure Accessories

Quantity 309.90 kg

Materials

Steel Plates 272.00 kg
Sagrod with nuts & Bolts 37.90 kg
Bolts and Rods 60.00 ea
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 4.00 days
1 Skilled Laborer 4.00 days
3 Laborer 4.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)b Fabricated Metal Roofing Accessory (Flashing, Ga. 26)

Quantity 29.00 l.m

Materials

Pre-painted flashing, Ga.24 (0.701mm) x 2.44mm 31.00 m
Blind Rivets 551.00 pc
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
1 Laborer 1.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)c Fabricated Metal Roofing Accessory (Gutter, Ga. 24)
Quantity 13.00 l.m

Materials

Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 13.00 m
12" x 1" Plain GI Strap 39.00 pc
Blind Rivets 208.00 pc
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
2 Laborer 1.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-2 Finishing Works

Quantity 49.50 sq.m

Materials

3mm Aluminum Composite Cladding Panel 21.00 pcs
Metal Furring 192.00 pc
Blind Rivets 2,700.00 pc
Drill Bit 7.00 box
Tubular 2"x2" 31.00 pc
SS Pipe 2" 2.00 pc
SS Pipe 1 1/2" 6.00 pc
Stainless Logo (SS 304) 1.00 lot
Stainless Lettering 26.00 pc
Building Marker-Outdoor (LEGAL) 1.00 pc
Welding Rod 5.00 kg
SS Welding Rod 2.00 kg
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 18.00 days
2 Skilled Laborer 18.00 days
2 Laborer 18.00 days

Equipment

1 Welding Machine, Electric Driven/DC Output, 500 Amp 12.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(8) Sewer Line Works

Quantity 1.00 l.s.

Materials

PVC Pipe, 100mm Ø x 3m, S-100 12.00 pcs
PVC Pipe, 150mm Ø x 3m, S-100 6.00 pcs
100mm Ø PVC Pipe Reducer 4.00 pcs
100mm Ø PVC Pipe Coupling 4.00 pcs
100mm Ø PVC 45deg elbow 4.00 pcs
Wye Reducer, 100mm dia.-75mm dia 4.00 pcs
Clean Out With Cover 100mm dia 8.00 pcs
Clean Out With Cover 75mm dia 8.00 pcs
PVC P-Trap, 50mm Dia 8.00 pcs
PVC Solvent Cement 20.00 cans
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 6.00 days
1 Skilled Laborer 6.00 days
3 Laborer 6.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(24) Cold Water lines

Quantity 1.00 l.s.

Materials

Booster Pump Motor 1.00 unit
Pressure Tank 42 gal 1.00 pcs
Reserved Tank 2000L 1.00 unit
PPR Union Patente 3/4" 4.00 pcs
PPR Union Patente 1/2" 8.00 pcs
PPR Male Connector 3/4" 10.00 pcs
PPR Male Connector 1/2" 8.00 pcs
PPR Valve 1/2" 6.00 pcs
PPR Valve 3/4" 3.00 pcs
PPR Elbow 1/2" Plain 61.00 pcs
PPR Elbow 3/4 Plain 37.00 pcs
PPR Elbow Female Thread 3/4" 8.00 pcs
PPR Elbow Male Thread 3/4" 8.00 pcs
PPR Coupling 3/4" 20.00 pcs
PPR Tee, 3/4" 26.00 pcs
PPR Reducer 3/4" x 1/2" 12.00 pcs
PPR Welding Machine 1.00 pcs
GI Plug 3/4" 2.00 pcs
GI Bushing 1 x 3/4" 8.00 pcs
Automatic Pressure Switch 1.00 pcs
Pressure Gauge 1.00 pcs
GI Pipe 4' x 1/4" 2.00 pcs
PPR Elbow 45 deg. 3/4 6.00 pcs
3R Breaker Set 1.00 pcs
#12 Stranded Wire 16.00 mtrs
PPR Pipe 1/2" 14.00 pcs
PPR Pipe 3/4" 20.00 pcs
Hose Bibb 4.00 pcs
Gate Valve 1.00 pcs
Check Valve 1.00 pcs
Float Valve 1/2 1.00 pcs
Water Meter 1.00 pcs
Cable Type Float Switch 1.00 pcs
Teflon Tape 10m 20.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 10.00 days
3 Skilled Laborer 10.00 days
3 Laborer 10.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(9) Storm Drainage and Downspout

Quantity 1.00 l.s.

Materials

100mm Ø PVC DS 9.00 pcs
100mm Ø PVC Pipe 90deg elbow 6.00 pcs
100mm Ø PVC Pipe Coupling 6.00 pcs
Roof Drain (Dome Type Strainer) 3.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 2.00 days
1 Skilled Laborer 2.00 days
1 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(4) Plumbing Fixtures

Quantity 1.00 l.s.

Materials

Water Closet inc. fittings & acc. (round) american std or equivalent 4.00 pcs
Lavatory inc. fittings & acc. American std or equivalent 4.00 pcs
Floor Drain 7.00 pcs
Shower Head with Valve Set 3.00 pcs
Consumables (5% of Material Cost) 1.00 lot

Labor

1 Foreman 6.00 days
2 Skilled Laborer 6.00 days
2 Laborer 6.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(11) Septic Vault/ Tank (Concrete / CHB)
Quantity 1.00 l.s.

Materials

Portland Cement 9.00 bags
Sand 1.00 cu.m
Gravel 3/4 1.00 cu.m
RSB Deformed Grade 40 191.55 kgs
Plastering 35.03 sq.m
Water Proofing Cement (Sahara Or Equivalent) 30.23 sq.m
CHB, 150 mm thk 267.00 pcs
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 4.00 days
2 Skilled Laborer 4.00 days
4 Laborer 4.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(5)b Catch Basin (CHB)
Quantity 3.00 each

Materials

Portland Cement 6.00 bags
Sand 5.00 cu.m
Gravel 3/4 5.00 cu.m
RSB Grade 40, 10 mm 34.00 kgs
#16 Galvanized Iron Wire 1.00 kgs
Metal Grating 14.00 kgs
CHB, Non Load Bearing, 4" 39.00 pcs
PVC Pipe, 100mm Ø x 3m, S-100 7.00 pcs
100mm Ø PVC Pipe Coupling 6.00 pcs
100mm Ø PVC 45deg elbow 4.00 pcs
Consumables (5% of Material Cost) 1.00 lot

Labor

1 Foreman 4.00 days
1 Skilled Laborer 4.00 days
2 Laborer 4.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-3 Electrical Works
Quantity 1.00 l.s.

Materials

100A, 2P, 230V MCCB 1.00 unit
30mm² THHN/THWN Wire 98.00 mtrs
5.5mm² THHN/THWN Wire 2.00 box
3.5mm² THHN/THWN Wire 3.00 box
2.0mm² THHN/THWN Wire 4.00 box
12w LED Round Recessed Pinlight Daylight 17.00 pcs
18w LED SQUARE Recessed Pinlight Daylight 39.00 pcs
14w LED Bulb Daylight with receptacle 8.00 pcs
Special Purpose Outlet 7.00 pcs

2 Gang Universal Type Outlet 29.00 pcs
 2 Gang Switch 2.00 pcs
 3 Gang Switch 6.00 pcs
 1 Gang Switch 6.00 pcs
 Junction Box 30.00 pcs
 UPVC Pipe 2" 17.00 pcs
 UPVC Pipe 1/2" 150.00 pcs
 PVC Locknot with bushing 1/2" 70.00 pcs
 Wall lamp 2.00 pcs
 Dyna Bolt 3/8 6.00 pcs
 Utility Box 44.00 pcs
 Panel board 20 branches with provision for MCCB Main 1.00 unit
 30Amp Breaker 14.00 pcs
 20 Amp breaker 4.00 pcs
 15 Amp Breaker 6.00 pcs
 Consumables (5% of Material Cost) 1.00 lot

Labor

1 Foreman 13.00 days
 4 Skilled Laborer 13.00 days
 2 Laborer 13.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1208 Fire Alarm System & Fire Extinguishers
 Quantity 1.00 l.s.

Materials

Manual Fire Alarm w/ Switch 2.00 set
 Manual Smoke Detector 10.00 pcs
 Fire Extinguisher 4.00 pcs

Labor

1 Foreman 3.00 days
 1 Skilled Laborer 3.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Construction of BFP Building	Construction of BFP Building	1	Lot	6,790,586.46

Pre-bid Conference

Date	Time	Venue
01/04/2026	10:00:00 AM	Office of the Bids and Awards Committee

Other Information

NOTE:

- In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.
- Interested bidders are advised to buy bidding documents at least a day before the opening of bids.

REMINDER:

In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

PREPARATION OF DOCUMENTS

- Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class "A" & Class "B") of documents in separate envelopes: Class "A" documents, containing the legal, technical & financial documents; and Class "B" documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).
- Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.
- Technical Documents must be ring bound with appropriate tabs.

4. Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

Created by Noreen A. Ortega
Date Created 24/03/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.