



## Bid Notice Abstract

### Invitation to Bid (ITB)

**Reference Number** 12948023  
**Procuring Entity** MUNICIPALITY OF TIAONG, QUEZON  
**Title** Construction of Brgy. Health Center at Brgy. Lagalag, Tiaong, Quezon  
**Area of Delivery** Quezon

<b>Solicitation Number:</b>	I-2026-04-10	<b>Status</b>	<b>Active</b>
<b>Trade Agreement:</b>	Implementing Rules and Regulations	<b>Associated Components</b>	3
<b>Procurement Mode:</b>	Public Bidding	<b>Bid Supplements</b>	0
<b>Classification:</b>	Civil Works	<b>Document Request List</b>	0
<b>Category:</b>	Construction Projects	<b>Date Published</b>	30/04/2026
<b>Approved Budget for the Contract:</b>	PHP 3,099,840.93	<b>Last Updated / Time</b>	30/04/2026 00:00 AM
<b>Delivery Period:</b>	120 Day/s	<b>Closing Date / Time</b>	19/05/2026 14:00 PM
<b>Client Agency:</b>			
<b>Contact Person:</b>	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851  noreenaortega@gmail.com		

<p><b>Description</b></p> <p>B.5 Project Billboard/Signboard Quantity: 1.00 each</p> <p>Materials: Ordinary Plywood ( 1/2" x 4' x 8') 2.00 pcs. Coco Lumber (2" x 3" x 12') 5.00 pcs. Tarpaulin (4' x 8') 1.00 unit Assorted CWN 1.00 kg.</p> <p>Labor: 1 Carpenter 0.50 day 2 Laborer 0.50 day</p> <p>B.7 Construction Safety and Health Quantity: 1.00 lot</p> <p>Materials Safety Helmet 15.00 pc(s) Hand Gloves 15.00 pair(s) Safety Shoes 15.00 pair(s) Misc (Medicine, Medicine Cabinet, Water, First Aid Kit) 1.00 lot</p> <p>803(1)a Structure Excavation, Common Soil Quantity: 28.16 cu.m</p> <p>Labor 1 Foreman 2.00 days 3 Laborer 2.00 days</p> <p>Equipment 1 Backhoe (0.80 cu.m) 2.00 hour 1 Dump Truck (12 cu.yd) 2.00 hour</p> <p>804(1)a Embankment from Structure Excavation Quantity: 25.88 cu.m</p> <p>Labor 1 Foreman 1.00 days 3 Laborer 1.00 days</p> <p>Equipment 1 Backhoe (0.80 cu.m) 3.00 hour 1 Plate Compactor 3.00 hour</p> <p>804(2)a Embankment from Borrow Quantity: 23.89 cu.m</p> <p>Materials Common Borrow 30.00 cu.m</p> <p>Labor 1 Foreman 1.00 day</p>
---

3 Laborer 1.00 day

Equipment

1 Backhoe (0.80 cu.m) 3.00 hour  
1 Plate Compactor 3.00 hour

804(7) Gravel Fill  
Quantity 10.16 cu.m

Materials

Gravel Fill 10.16 cu.m

Labor

1 Foreman 2.00 days  
3 Laborer 2.00 days

Equipment

1 Plate Compactor 8.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

900(1)d Structural Concrete (4000 psi, Class A, 28 days)  
Quantity 16.57 cu.m

Materials

Ready Mix Concrete 4000Psi @ 28 Days 18.00 cu.m

Labor

1 Foreman 3.00 days  
2 Skilled Laborer 3.00 days  
6 Laborer 3.00 days

Equipment

2 Concrete Vibrator 8.00 hour  
1 Pumpcrete 4.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

900(1)c Structural Concrete (3000 psi, Class A, 28 days)  
Quantity 9.84 cu.m

Materials

Ready Mix Concrete 3000Psi @ 28 Days 11.00 cu.m

Labor

1 Foreman 2.00 days  
2 Skilled Laborer 2.00 days  
6 Laborer 2.00 days

Equipment

2 Concrete Vibrator 6.00 hour  
1 Pumpcrete 3.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

902(1)a1 Reinforcing Steel (Deformed) Grade 40  
Quantity 1,161.80 kg

Materials

Reinforcing Steel Bars Deformed Grade 40 1,220.00 kg  
GI Tie Wire #16 19.00 kg

Labor

1 Foreman 2.00 days  
3 Skilled Laborer 2.00 days  
8 Laborer 2.00 days

Equipment

1 Bar Cutter 4.00 hour  
1 Bar Bender 4.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

902(1)a2 Reinforcing Steel (Deformed) Grade 60  
Quantity 923.98 kg

Materials

Reinforcing Steel Bars Deformed Grade 60 971.00 kg  
GI Tie Wire #16 15.00 kg

Labor

1 Foreman 2.00 days  
3 Skilled Laborer 2.00 days  
8 Laborer 2.00 days

Equipment

1 Bar Cutter 4.00 hour  
1 Bar Bender 4.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

903(2) Formworks and Falseworks  
Quantity 138.05 sq.m

Materials

Phenolic Board - 1.22m x 2.44m x 18mm (5 uses) 10.00 pc  
Good Lumber 218.00 bd.ft  
Consumables (1% of Materials Cost) 1.00 lot

Labor

1 Foreman 2.00 days  
1 Skilled Laborer 2.00 days  
1 Laborer 2.00 days  
Stripping  
2 Laborer 2.00 days

Equipment

40 H-Frame 1.7 m x 1.2m, set 8.00 hrs  
2pcs H-frames  
4pcs diagonal cross braces  
4pcs Horizontal cross braces  
8pcs joint pins  
62 Shoring Jack, 3.8 m full extension 8.00 hrs  
80 Adj. U-Head Jack, 0.60m 8.00 hrs  
80 Adj. Base Jack, 0.60m 8.00 hrs  
62 1-1/2" GI Pipe x 6.0 m 8.00 hrs  
16 1-1/2" GI Pipe x 3.0 m 8.00 hrs  
32 1-1/2" GI Pipe x 4.0 m 8.00 hrs  
216 1-1/2" GI Pipe x 1.0 m 8.00 hrs  
278 Tie Rod x 0.60m 8.00 hrs  
558 Round Wing Not 8.00 hrs

1000(1) Soil Poisoning  
Quantity 3.00 liter

Materials  
Soil Poisoning 3.00 lit

Labor  
1 Foreman 0.50 day  
1 Laborer 0.50 day

Equipment  
1 Minor Tools (10% of Labor Cost) 1.00 lot

1046(2)a1 CHB Non-Load Bearing (including Reinforcing Steel), 100mm  
Quantity 58.44 sq.m

Materials  
CHB Ordinary (101mm x 203mm x 406mm) 760.00 pcs  
Portland Cement 31.00 bag  
Sand 3.00 cu.m  
Reinforcing Steel Bars Deformed Grade 40 190.00 kg  
GI Tie Wire #16 3.00 kg

Labor  
1 Foreman 2.00 days  
2 Skilled Laborer 2.00 days  
2 Laborer 2.00 days

Equipment  
1 One Bagger Mixer 16.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

1046(2)a2 CHB Non-Load Bearing (including Reinforcing Steel), 150mm  
Quantity 107.65 sq.m.

Materials  
CHB Ordinary (150mm x 230mm x 406mm) 1,400.00 pcs  
Portland Cement 58.00 bag  
Sand 5.00 cu.m  
Reinforcing Steel Bars Deformed Grade 40 349.00 kg  
GI Tie Wire #16 6.00 kg

Labor  
1 Foreman 5.00 days  
2 Skilled Laborer 5.00 days  
2 Laborer 5.00 days

Equipment  
1 One Bagger Mixer 34.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

1010(2)a Doors, Flush  
Quantity 9.45 sq.m.

Materials  
Flush Hollow Core Door with Door Jamb 5.04 sq.m  
PVC Swing Door with Door Jamb 4.41 sq.m  
Door Locks (Schlage or Equivalent) 7.00 set  
Door Hinge (50mm x 101mm) 28.00 pc  
Consumables (5% of Material Cost)

Labor  
1 Foreman 4.00 days  
1 Skilled Laborer 4.00 days  
1 Laborer 4.00 days

1010(2)c Doors (Glass Panel)  
Quantity 3.78 sq.m

Materials  
Sliding Door Panel with complete accessories 3.78 sq.m  
Consumables (5% of Material Cost)

Labor  
1 Foreman 2.00 days  
1 Skilled Laborer 2.00 days  
1 Laborer 2.00 days

1008(1)c Aluminum Glass Window (Awning Type)  
Quantity 11.32 sq.m

Materials  
Aluminum framed Glass Window (Awning Type) 11.32 sq.m

Labor  
1 Foreman 3.00 days  
1 Skilled Laborer 3.00 days

1 Laborer 3.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1027(1) Cement Plaster Finish  
Quantity 474.08 sq.m

Materials

Portland Cement 157.00 bag  
Sand 13.00 cu.m

Labor

1 Foreman 7.00 days  
2 Skilled Laborer 7.00 days  
2 Laborer 7.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1003(1)a1 Ceiling (4.5mm, Metal Frame, Fiber Cement Board)  
Quantity 108.68 sq.m

Materials

15mm thick Armstrong Acoustic Ceiling/Fiber Cement Board 40.00 pcs  
Metal Furring 123.00 pcs  
Carrying Channels 39.00 pcs  
Hanger Bars/Rod 109.00 pcs  
Channel clip 653.00 pcs  
Wall Angle 26.00 pcs  
Rivets 1,522.00 pcs  
1" Metal Screw 435.00 pcs

Labor

1 Foreman 10.00 days  
1 Skilled Laborer 10.00 days  
2 Laborer 10.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1038(1) Reflective Insulation  
Quantity 108.68 sq.m

Materials

Reflective Insulation, 10 mm thk 109.00 sq.m  
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 2.00 days  
1 Skilled Laborer 2.00 days  
1 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1018(1) Glazed Tiles  
Quantity 89.27 sq.m

Materials

Ceramic Glazed Tiles 92.00 sq.m  
Portland Cement 30.00 bags  
Sand 3.00 cu.m  
Tile Grout 11.00 bags  
Consumables (2% of Material Cost) 1.00 lot

Labor

1 Foreman 6.00 days  
3 Skilled Laborer 6.00 days  
3 Laborer 6.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1018(2) Unglazed Tiles  
Quantity 32.41 sq.m

Materials

Ceramic Unglazed Tiles 34.00 sq.m  
Portland Cement 11.00 bags  
Sand 1.00 cu.m  
Tile Grout 5.00 bags  
Consumables (2% of Material Cost) 1.00 lot

Labor

1 Foreman 2.00 days  
2 Skilled Laborer 2.00 days  
3 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-I Finishing Works  
Quantity 1.00 lot

Materials

Decorative Red Brick 1.00 lot  
Acrylic Lettering 1.00 lot  
Consumables (5% of Material Cost) 1.00 lot

Labor

1 Foreman 3.00 days

1 Skilled Laborer 3.00 days  
2 Laborer 3.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1032(1)a Painting Works (Masonry/Concrete)  
Quantity 474.08 sq.m

Materials

Concrete Neutralizer 10.00 gal  
Concrete Sealer/Primer 19.00 gal  
Patching Compound 24.00 gal  
Semi-Gloss Latex (2 coats only) 38.00 gal  
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 8.00 days  
2 Skilled Laborer 8.00 days  
1 Laborer 8.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1032(1)c Painting Works (Steel)  
Quantity 276.43 sq.m

Materials

Red Oxide Primer 12.00 gal  
Flat Wall Enamel 28.00 gal  
Paint Thinner 70.00 liter  
Tinting Color 3.00 liter  
Consumables 1.00 lot

Labor

1 Foreman 9.00 days  
2 Skilled Laborer 9.00 days  
1 Laborer 9.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1014(1)b2 Prepainted Metal Sheets (above 0.427mm) Rib Type Long Span  
Quantity 109.16 sq.m.

Materials

Long Span Rib Type Colored Roof, Ga. 26 115.00 sq.m.  
Tekscrow 1,092.00 pcs  
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 6.00 days  
2 Skilled Laborer 6.00 days  
2 Laborer 6.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(7) Structural Steel  
Quantity 1.00 l.s

Materials

Structural Steel Truss 1,342.74 kg  
Acetylene 15.00 kg  
Oxygen 30.00 kg  
Welding Rod 27.00 kg  
Consumables Materials (1% of Matl. Cost) 1.00 lot

Labor

1 Foreman 4.00 days  
2 Skilled Laborer 4.00 days  
2 Laborer 4.00 days

Erection

1 Skilled Laborer 4.00 days  
2 Laborer 4.00 days

Equipment

1 Welding Machine, Electric Driven/DC Output, 500 Amp 20.00 hours  
1 Cutting Outfit 14.00 hours  
1 Grinding Machine and Accessories 20.00 hours  
1 Cargo/Service Truck, 2-5 mt, 160 hp 4.00 hours  
1 Boom Truck, NXG1160D3ZAL1X, 197 hp 5.00 hours  
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(8)b Structural Steel (Purlins)  
Quantity 2,746.94 kg

Materials

Structural Steel Purlins 2,775.00 kg  
Welding Rod 55.00 kg  
Consumables (1% of Materials Cost) 1.00 lot

Labor

1 Foreman 6.00 days  
2 Skilled Laborer 6.00 days  
4 Laborer 6.00 days

Equipment

2 Welding Machine, Electric Driven/DC Output, 500 Amp 37.00 hour  
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(5) Metal Structure Accessories

Quantity 626.84 kg

Materials

Steel Plates 559.78 kg  
Sagrod with nuts & Bolts 32.31 kg  
Cross Bracing 34.76 kg  
16mm Ø turn buckles 10.00 pc  
Bolts and Rods 68.00 ea  
Consumables (1% of Materials Cost) 1.00 lot

Labor

1 Foreman 7.00 days  
1 Skilled Laborer 7.00 days  
2 Laborer 7.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)b Fabricated Metal Roofing Accessory (Flashing, Ga. 26)  
Quantity 32.40 l.m

Materials

Pre-painted flashing, Ga.24 (0.701mm) x 2.44mm 35.00 m  
Blind Rivets 616.00 pc  
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 1.00 days  
1 Skilled Laborer 1.00 days  
1 Laborer 1.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)c Fabricated Metal Roofing Accessory (Gutter, Ga. 24)  
Quantity 32.40 l.m

Materials

Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 33.00 m  
12" x 1" Plain GI Strap 98.00 pc  
Blind Rivets 519.00 pc  
Consumables (3% of Materials Cost) 1.00 lot

Labor

1 Foreman 1.00 days  
1 Skilled Laborer 1.00 days  
2 Laborer 1.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(8) Sewer Line Works  
Quantity 1.00 l.s.

Materials

PVC Pipe, 100mm Ø x 3m 8.00 pcs  
PVC Pipe, 50mm Ø x 3m 10.00 pcs  
Reducer 100mm x 50mm 5.00 pcs  
WYE 100 mm 3.00 pcs  
Elbow 100 mm 3.00 pcs  
PVC Pipe, 50 mm Elbow 1.00 lot  
Sanitary Tee 50 mm 6.00 pcs  
Coupling 50 mm 9.00 pcs  
P-Trap 8.00 pcs  
Cleanout 3.00 pcs  
PVC Solvent Cement 5.00 pcs  
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 3.00 days  
1 Skilled Laborer 3.00 days  
2 Laborer 3.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(24) Cold Water lines  
Quantity 1.00 l.s.

Materials

PPRC CWL, 32mm Ø X 4m 7.00 pcs  
PPRC CWL, 50mm Ø X 4m 2.00 pcs  
PPRC CWL Coupling, 32mm Ø 7.00 pcs  
PPRC CWL Elbow 90 deg, 32mm Ø 9.00 pcs  
PPRC CWL Elbow 90 deg, 50mm Ø 4.00 pcs  
PPRC CWL Tee, 32mm Ø 7.00 pcs  
PPRC CWL Reducer coupling, 32mm Ø x 50mm Ø 2.00 pcs  
Male/Female Adapter 10.00 pcs  
Ball Valve 32mm 2.00 pcs  
Teflon Tape 10.00 pcs  
Hose Bibb 2.00 pcs  
Gate valve 1.00 pcs  
Check Valve 1.00 pcs  
Water meter 1.00 pcs  
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 2.00 days  
1 Skilled Laborer 2.00 days  
2 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(9) Storm Drainage and Downspout  
Quantity 1.00 l.s.

Materials

100mm Ø PVC DS 8.00 pcs  
100mm Ø PVC Pipe 90deg elbow 8.00 pcs  
100mm Ø PVC Pipe Coupling 6.00 pcs  
Roof Drain (Dome Type Strainer) 4.00 pcs  
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 2.00 days  
1 Skilled Laborer 2.00 days  
1 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(4) Plumbing Fixtures  
Quantity 1.00 l.s.

Materials

Water Closet inc. fittings & acc. (round) american std or equivalent 3.00 pcs  
Lavatory inc. fittings & acc. American std or equivalent 4.00 pcs  
Floor Drain 6.00 pcs  
Shower Head with Valve Set 1.00 pcs  
Consumables (3% of Material Cost) 1.00 lot

Labor

1 Foreman 6.00 days  
2 Skilled Laborer 6.00 days  
2 Laborer 6.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(11) Septic Vault/ Tank (Concrete / CHB)  
Quantity 1.00 l.s.

Materials

Portland Cement 9.00 bags  
Sand 1.00 cu.m  
Gravel 3/4 1.00 cu.m  
RSB Deformed Grade 40 192.00 kgs  
Plastering 35.00 sq.m  
Water Proofing Cement (Sahara Or Equivalent) 30.50 sq.m  
CHB, 150 mm thk 267.00 pcs  
Consumables (5% of Materials Cost) 1.00 lot

Labor

1 Foreman 4.00 days  
1 Skilled Laborer 4.00 days  
2 Laborer 4.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(5)b Catch Basin (CHB)  
Quantity 4.00 each

Materials

Portland Cement 8.00 bags  
Sand 1.00 cu.m  
Gravel 3/4 1.00 cu.m  
RSB Grade 40, 10 mm 45.00 kgs  
#16 Galvanized Iron Wire 1.00 kgs  
Metal Grating 19.00 kgs  
CHB, Non Load Bearing, 4" 52.00 pcs

Labor

1 Foreman 2.00 days  
1 Skilled Laborer 2.00 days  
1 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1100(10) Conduits, Boxes & Fittings (Conduit Works/Conduit Rough-in)  
Quantity 1.00 l.s.

Materials

20 mmØ uPVC conduit 120.00 l.m  
20 mmØ PVC Adapter 40.00 l.m  
Utility box, deep type 40.00 pc  
junction box, deep type 20.00 pc  
Consumables 1.00 lot

Labor

1 Foreman 2.00 days  
1 Skilled Laborer 2.00 days  
2 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

1101(33) Wires and Wiring Devices  
Quantity 1.00 l.s.

Materials

Electric Wires THWN/THNN 5.5 mm<sup>2</sup> 120.00 l.m.

One-gang Switch 6.00 set  
 Two-Gang Switch 2.00 set  
 Three-Gang Switch 2.00 set  
 Duplex Convenience Outlet 10.00 set  
 Heavy Duty Outlet 1.00 set  
 Tape, bolt&nut, mica tube, terminal lugs, etc. 1.00 lot  
 JB cover clamps, screw and anchors  
 Consumables (5% of Materials Cost) 1.00 lot

**Labor**

1 Foreman 2.00 days  
 1 Skilled Laborer 2.00 days  
 3 Laborer 2.00 days

**Equipment**

1 Minor Tools (10% of Labor Cost) 1.00 lot

1102(1) Panelboard with Main & Branch Breakers  
 Quantity 1.00 l.s.

**Materials**

Enclosed Air Circuit Breaker 1.00 lot  
 Panelboard & Cabinets 1.00 lot  
 Consumables (5% of Materials Cost)

**Labor**

1 Foreman 2.00 days  
 1 Skilled Laborer 2.00 days  
 2 Laborer 2.00 days

**Equipment**

1 Minor Tools (10% of Labor Cost) 1.00 lot

1103(1) Lighting Fixtures  
 Quantity 1.00 l.s.

**Materials**

12 watts Ceiling-mounted LED Box-type light 20.00 set  
 2-20W Emergency Light 4.00 set  
 Consumables (5% of Materials Cost) 1.00 lot

**Labor**

1 Foreman 2.00 days  
 2 Skilled Laborer 2.00 days  
 2 Laborer 2.00 days

**Equipment**

1 Minor Tools (10% of Labor Cost) 1.00 lot

**Line Items**

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Construction of Brgy. Health Center	Brgy. Lagalag, Tiaong, Quezon	1	Lot	3,099,840.93

**Pre-bid Conference**

Date	Time	Venue
07/05/2026	10:00:00 AM	Office of the Bids and Awards Committee

**Other Information**

**NOTE:**

1. In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.
2. Interested bidders are advised to buy bidding documents at least a day before the opening of bids.

**REMINDER:**

In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

**PREPARATION OF DOCUMENTS**

1. Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class "A" & Class "B") of documents in separate envelopes: Class "A" documents, containing the legal, technical & financial documents; and Class "B" documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).
2. Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.
3. Technical Documents must be ring bound with appropriate tabs.
4. Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

**Created by** Noreen A. Ortega

**Date Created** 28/04/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.