



Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number 12949047
Procuring Entity MUNICIPALITY OF TIAONG, QUEZON
Title Improvement of Multi-Purpose Building for Child Development Center at Brgy. Palagaran, Tiaong, Quezon
Area of Delivery Quezon

Solicitation Number:	I-2026-04-12	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	4
Procurement Mode:	Public Bidding	Bid Supplements	0
Classification:	Civil Works	Document Request List	0
Category:	Construction Projects	Date Published	30/04/2026
Approved Budget for the Contract:	PHP 1,497,514.29	Last Updated / Time	30/04/2026 00:00 AM
Delivery Period:	70 Day/s	Closing Date / Time	07/05/2026 14:00 PM
Client Agency:			
Contact Person:	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851 noreenaortega@gmail.com		

Description

605 Project Billboard/Signboard
Quantity: 5.76 sq.m

Materials:

Ord. Plywood # 1/2 x 4 x 8 2.00 pcs
Coco Lumber (2 x 3 x 8) 5.00 pcs
Tarpaulin (8' x 8') 1.00 unit
Assorted CWN 1.00 kls

Labor:

1 Carpenter 0.50 day
1 Laborer 0.50 day

SPL-1 Occupational Safety & Health Program
Quantity: 1.00 lot

Materials:

Safety Helmet 12.00 pcs
Hand Gloves 12.00 pair
Safety Shoes 12.00 pair
Miscellaneous Items 1.00 lot
(Medicine, Medicine Cabinet, Water, First-Aid Kit)

103 Structure Excavation
Quantity: 4.50 cu.m

Labor:

1 Skilled Worker 1.00 day
3 Laborer 1.00 day

Equipments:

Minor Tools (10% of Labor Cost)

804(1)a Embankment from Structure Excavation
Quantity: 4.40 cu.m

Labor:

1 Construction Foreman 1.00 day
1 Laborer 1.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-2 Demolition
Quantity: 1.00 lot

Labor:

3 Skilled Worker 3.00 day

3 Laborer 3.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-3 Reinforced Concrete and Masonry Works

Quantity: 1.00 lot

Materials:

Cement 185.00 pcs

Sand 14.00 cu.m

Gravel 10.00 cu.m

CHB#4 1,446.00 pcs

RSB 12mm 80.00 pcs

RSB 10mm 170.00 pcs

Ordinary Plywood 1/2" 15.00 pcs

Coco lumber 280.00 bd.ft

Tie Wire 14.00 kgs

Consumables 1.00 lot

Labor:

1 Construction Foreman 14.00 day

3 Skilled Worker 14.00 day

4 Laborer 14.00 day

Equipments:

1 One Bagger Mixer 40.00 hrs

Minor Tools (10% of Labor Cost)

SPL-4 Roofing Works

Quantity: 107.15 sq.m

Materials:

Long Span Rib Type Colored Roof, Ga. 26 112.51 sq.m.

Angle Bar 2x2x4.5mm 33.00 pcs

Channel Bar (2"x4"x20') 9.00 pcs

C-Purlins (2"x4"x20') 35.00 pcs

C-Purlins (2"x6"x20') 11.00 pcs

Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 5.00 pcs

G.I. Pipe Sch. 40 2" 2.00 pcs

12" x 1" Plain GI Strap 33.00 pcs

Colored Plain Sheet (4x8) Ga.22 8.00 pcs

Welding Rod 8.00 kgs

Texscrew 500.00 pcs

Cutting Disc 2.00 box

PVC Pipe 3" 5.00 pcs

PVC Elbow 3" 6.00 pcs

Consumables (2% of Materials) 1.00 lot

Labor:

1 Construction Foreman 11.00 day

3 Skilled Worker 11.00 day

4 Laborer 11.00 day

Equipments:

Welding Machine 16.00 hours

Minor Tools (10% of Labor Cost)

1003 Ceiling Works

Quantity: 80.60 sq.m

Materials:

Hardieflex 4' x 8' 35.00 pcs

Wall Angle 0.6mm x 3m 38.00 pcs

Carrying Channel 0.8mm x 5m 27.00 pcs

Double Furring Channel 0.5mm x 5m 33.00 pcs

Double Furring Clip 280.00 pcs

Black TekscREW 3.00 box

Perforated Paper Tape 2" x 250' 1.00 roll

Assorted CWN 1.00 kgs

Latex Paint 8.00 gal

Paint Brush 2" 3.00 pcs

Paint Roller 7" with tray 3.00 pcs

Blind Rivets 7.00 box

Hardieflex Scoring Knife 2.00 pcs

Consumables (5% of Materials)

Labor:

1 Construction Foreman 4.00 day

3 Skilled Worker 4.00 day

3 Laborer 4.00 day

1032 Paint Works

Quantity: 245.00 sq.m

Materials:

Concrete Neutralizer 5.00 gal

Skimcoat 16.00 bags

Primer Flat Latex 21.00 gal

Top Coat Latex 23.00 gal

Gray Metal Primer 4.00 gal

Enamel Paint 2.00 gal

Paint Brush 4" 4.00 pcs

Paint Brush 2" 4.00 pcs

Paint Roller 7" with tray 4.00 pcs

Sand Paper #100 10.00 meter

Mesh Tape 5.00 pcs

Consumables (5% of Materials) 1.00 lot

Labor:
3 Skilled Worker 5.00 day
3 Laborer 5.00 day

SPL-6 Finishing
Quantity: 1.00 lot

Materials:
Tubular 2" x 1" 4.00 pcs
Tubular 1" x 1" 9.00 pcs
Cylindrical Hinges 3.00 pcs
Barrel Lock with Accessories 1.00 pcs
Wire Mesh 1"x4' Ga.16 13.50 m
Welding Rod 3.00 kgs
Acrylic Lettering 1.00 lot
Consumables (5% of Materials) 1.00 lot

Labor:
2 Skilled Worker 3.00 day
2 Laborer 3.00 day

Equipments:
1 Welding Machine 4.00 hours
Minor Tools (10% of Labor Cost)

1018 Tile Works
Quantity: 76.44 sq.m

Materials:
60cm x 60 cm Tiles 202.00 pcs
30cm x 30 cm Tiles 196.00 pcs
Tile Adhesive 27.00 bags
Tile Grout 22.00 bags
Consumables (2% of Materials) 1.00 lot

Labor:
1 Construction Foreman 10.00 day
2 Skilled Worker 10.00 day
2 Laborer 10.00 day

Equipments:
Minor Tools (10% of Labor Cost)

SPL-5 Doors & Windows
Quantity: 1.00 l.s

Materials:
"Glass Door, Swing type, Complete w/
Accessories 6mm (2.1x1.6)" 3.36 sq.m
Analok Glass Window with Frame and acc. 8.96 sq.m
Flush Hollow Core Door with Door Jamb 3.78 sq.m
PVC Swing Door with Door Jamb 2.94 sq.m
Door Locks (Schlage or Equivalent) 4.00 set
Door Hinge (50mm x 101mm) 16.00 pc
Window Grills 149.51 sq.ft
Consumables 1.00 lot

Labor:
2 Skilled Worker 2.00 day
2 Laborer 2.00 day

1002(4) Plumbing Fixtures
Quantity 1.00 l.s.

Materials
"Water Closet inc. fittings & acc. (round)
american std or equivalent" 2.00 pcs
Floor Drain 3.00 pcs
Stainless Sink-Double 1.00 pcs
Deck Mounted Faucet 1.00 pcs
Stainless Wall Faucet 5.00 pcs
Consumables (5% of Material Cost) 1.00 lot

Labor
2 Skilled Laborer 1.00 days
2 Laborer 1.00 days

Equipment
Minor Tools (10% of Labor Cost)

SPL-7 Water & Sewer Line Works
Quantity 1.00 l.s.

Materials
PVC Pipe, 100mm Ø x 3m, S-100 5.00 pcs
PVC Pipe, 50mm Ø x 3m, S-100 8.00 pcs
100mm Ø PVC Pipe Coupling 4.00 pcs
50mm Ø PVC Pipe Coupling 4.00 pcs
PVC Elbow 90 deg. 100mm Ø 5.00 pcs
PVC Wye 100mm Ø 3.00 pcs
PVC Elbow 90 deg. 50mm Ø 3.00 pcs
PVC Elbow 45 deg. 50mm Ø 3.00 pcs
PVC Tee 100mm Ø 2.00 pcs
PVC Tee 50mm Ø 2.00 pcs
PVC Sanitary Clean Out 100mm Ø 2.00 pcs
PVC Solvent Cement 2.00 cans
PPR Coupling 3/4" 10.00 pcs
PPR Coupling 1" 6.00 pcs
PPR Tee, 3/4" 6.00 pcs

PPR Tee, 1" 2.00 pcs
 PPR Elbow 3/4" Plain 14.00 pcs
 PPR Elbow 1" Plain 4.00 pcs
 PPR Reducer 1" x 3/4" 3.00 pcs
 PPR Pipe 1" 5.00 pcs
 PPR Pipe 3/4" 5.00 pcs
 Gate Valve 1.00 pcs
 Teflon Tape 10m 5.00 pcs
 Consumables (5% of Materials) 1.00 lot

Labor
 2 Skilled Laborer 2.00 days
 2 Laborer 2.00 days

Equipment
 Minor Tools (10% of Labor Cost)

SPL-8 Electrical Works
 Quantity: 1.00 l.s

Materials:
 1 Gang switch 2.00 pc
 2 Gang switch 1.00 pcs
 3 Gang switch 1.00 pcs
 2.0mm2 wire 1.00 box
 3.5mm2 wire 90.00 mtrs
 5.5mm2wire 36.00 mtrs
 Flexible hose 1.50 pcs
 Plastic Molding 1/2 26.00 pcs
 Junction Box 15.00 pcs
 Special Purpose Outlet 1.00 pcs
 AMCO Box 15.00 pcs
 2 Gang Universal Type Outlet 6.00 pcs
 3 Gang C.O 2.00 roll
 T8 18w Louver Type Double Tube Fluorescent Daylight 6.00 pcs
 14 led bulb with receptacle 4.00 unit
 Panel board-8 slot 1.00 pcs
 15AT Circuit Breaker 1.00 unit
 20AT Circuit Breaker 2.00 pc
 30AT Circuit Breaker 1.00 pc
 30AT Circuit Breaker with cover 2.00 pc
 60AT Circuit Breaker 1.00 pcs
 2 HP Split Type ACU 1.00 pcs
 Locknut Bushing 50.00 lot
 Consumables (3% of Materials) 1.00 lot

Labor:
 1 Construction Foreman 5.00 day
 4 Skilled Worker 5.00 day
 2 Laborer 5.00 day

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Improvement of Multi-Purpose Building	For Child Development Center at Brgy. Palagaran, Tiaong, Quezon	1	Lot	1,497,514.29

Other Information

NOTE:

- In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.
- Interested bidders are advised to buy bidding documents at least a day before the opening of bids.

REMINDER:

In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

PREPARATION OF DOCUMENTS

- Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class "A" & Class "B") of documents in separate envelopes: Class "A" documents, containing the legal, technical & financial documents; and Class "B" documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).
- Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.
- Technical Documents must be ring bound with appropriate tabs.
- Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

Created by Noreen A. Ortega

Date Created 29/04/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.