



Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number 13001135
Procuring Entity MUNICIPALITY OF TIAONG, QUEZON
Title Improvement of Multi-Purpose Building for Child Development Center at Brgy. Bukal, Tiaong, Quezon
Area of Delivery Quezon

Solicitation Number:	I-2026-05-04	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	4
Procurement Mode:	Public Bidding	Bid Supplements	0
Classification:	Civil Works	Document Request List	0
Category:	Construction Projects	Date Published	21/05/2026
Approved Budget for the Contract:	PHP 1,197,253.73	Last Updated / Time	21/05/2026 00:00 AM
Delivery Period:	60 Day/s	Closing Date / Time	28/05/2026 15:00 PM
Client Agency:			
Contact Person:	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851 noreenaortega@gmail.com		

Description

B.5 Project Billboard/Signboard
Quantity: 5.76 sq.m

Materials:

Ord. Plywood # 1/2 x 4 x 8 2.00 pcs
Coco Lumber (2 x 3 x 8) 5.00 pcs
Tarpaulin (8' x 8') 1.00 unit
Assorted CWN 1.00 kls

Labor:

1 Carpenter 0.50 day
1 Laborer 0.50 day

B.7 Occupational Safety & Health Program
Quantity: 1.00 lot

Materials:

Safety Helmet 9.00 pcs
Hand Gloves 9.00 pair
Safety Shoes 9.00 pair
Miscellaneous Items 1.00 lot
(Medicine, Medicine Cabinet, Water, First-Aid Kit)

103 Structure Excavation
Quantity: 13.50 cu.m

Labor:

1 Skilled Worker 3.00 day
3 Laborer 3.00 day

Equipments:

Minor Tools (10% of Labor Cost)

104 Embankment

Quantity: 1.50 cu.m

Labor:

1 Skilled Worker 1.00 day

2 Laborer 1.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-1 Demolition

Quantity: 1.00 lot

Labor:

3 Skilled Worker 1.00 day

3 Laborer 1.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-2 Reinforced Concrete and Masonry Works

Quantity: 1.00 lot

Materials:

Cement 40.00 pcs

Sand 3.00 cu.m

Gravel 2.00 cu.m

CHB 4" 280.00 pcs

RSB 10mm 30.00 pcs

Tie Wire 5.00 kgs

Consumables (5% of Materials) 1.00 lot

Labor:

1 Construction Foreman 4.00 day

2 Skilled Worker 4.00 day

2 Laborer 4.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-3 Roofing Works

Quantity: 92.90 sq.m

Materials:

Long Span Rib Type Colored Roof, Ga. 26 97.55 sq.m.

Angle Bar 2x2x4.5mm 53.00 pcs

C-Purlins (2"x4"x20') 37.00 pcs

C-Purlins (2"x6"x20') 5.00 pcs

Channel Bar (2"x4"x20') 8.00 pcs

Flat bar (2"x6mm) 2.00 pcs

Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 6.00 pcs

Colored Plain Sheet (4x8) Ga.22 4.00 pcs

12" x 1" Plain GI Strap 37.00 pcs

Welding Rod 15.00 kgs

Texscrew 1,200.00 pcs

Cutting Disc 3.00 box

PVC Pipe 3" 6.00 pcs

PVC Elbow 3" 4.00 pcs

Consumables (2% of Materials) 1.00 lot

Labor:(including the dismantling of existing roof)

1 Construction Foreman 15.00 day

3 Skilled Worker 15.00 day

3 Laborer 15.00 day

Equipments:

1 Welding Machine 24.00 hours

Minor Tools (10% of Labor Cost)

1003 Ceiling Works

Quantity: 62.40 sq.m

Materials:

Hardieflex 4' x 8' 24.00 pcs

Wall Angle 0.6mm x 3m 33.00 pcs

Carrying Channel 0.8mm x 5m 38.00 pcs

Double Furring Channel 0.5mm x 5m 33.00 pcs
Double Furring Clip 195.00 pcs
Black Teksew 3.00 box
Perforated Paper Tape 76m/roll 1.00 roll
Assorted CWN 1.00 kgs
Acrylic Latex Paint 5.00 gal
Paint Brush 2" 2.00 pcs
Paint Roller 7" with tray 2.00 pcs
Blind Rivets 5.00 box
Hardieflex Scoring Knife 1.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor:

1 Construction Foreman 4.00 day
2 Skilled Worker 4.00 day
3 Laborer 4.00 day

1032 Paint Works
Quantity: 228.60 sq.m

Materials:

Primer Flat Latex 19.00 gal
Top Coat Latex 20.00 gal
Gray Metal Primer 19.00 gal
Enamel Paint 5.00 gal
Paint Brush 4" 6.00 pcs
Paint Brush 2" 4.00 pcs
Paint Roller 7" with tray 4.00 pcs
Sand Paper #100 10.00 meter
Mesh Tape 5.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor:

3 Skilled Worker 6.00 day
3 Laborer 6.00 day

1018 Tile Works
Quantity: 58.00 sq.m

Materials:

60cm x 60 cm Tiles (Non-skid) 154.00 pcs
30cm x 30 cm Tiles(Non-skid) 182.00 pcs
Cement 9.00 pcs
Sand 1.00 cu.m
Tile Adhesive 16.00 bags
Tile Grout 19.00 bags
Consumables (2% of Materials) 1.00 lot

Labor:

1 Construction Foreman 9.00 day
2 Skilled Worker 9.00 day
2 Laborer 9.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-4 Finishing Works
Quantity: 1.00 lot

Materials:

Tubular 2" x 2" 17.00 pcs
Tubular 1" x 1" 23.00 pcs
Welded Wire Mesh 10.00 pcs
Cylindrical Hinges 10.00 pcs
Caster Wheel Heavy Duty 2.00 pcs
Barrel Lock with Accessories 1.00 pcs
Welding Rod 10.00 kgs
Acrylic Lettering 1.00 lot
Consumables (5% of Materials) 1.00 lot

Labor:

3 Skilled Worker 5.00 day
3 Laborer 5.00 day

Equipments:

1 Welding Machine 16.00 hours
Minor Tools (10% of Labor Cost)

SPL-5 Doors & Windows

Quantity: 1.00 l.s

Materials:

Flush Hollow Core Door with Door Jamb 1.89 sq.m
PVC Swing Door with Door Jamb 3.78 sq.m
Door Locks (Schlage or Equivalent) 1.00 set
Door Hinge (50mm x 101mm) 4.00 pc
Consumables 1.00 lot

Labor:

2 Skilled Worker 1.00 day
2 Laborer 1.00 day

1002(4) Plumbing Fixtures

Quantity 1.00 l.s.

Materials

"Water Closet inc. fittings & acc. (round)
american std or equivalent" 2.00 pcs
Floor Drain 2.00 pcs
Stainless Sink-Double 1.00 pcs
Deck Mounted Faucet 1.00 pcs
Bidet Set 2.00 pcs
Stainless Wall Faucet 6.00 pcs
Consumables (5% of Material Cost) 1.00 lot

Labor

1 Foreman 2.00 days
2 Skilled Laborer 2.00 days
2 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-6 Water & Sewer Line Works (Including Septic Tank)

Quantity 1.00 l.s.

Materials

Cement 50.00 pcs
Sand 5.00 cu.m
Gravel 3/4 2.00 cu.m
RSB 12mm 5.00 pcs
RSB 10mm 42.00 pcs
CHB 6" 234.00 pcs
Liquid Asphalt 2.00 gal
PVC Pipe, 100mm Ø x 3m, S-100 7.00 pcs
PVC Pipe, 50mm Ø x 3m, S-100 6.00 pcs
100mm Ø PVC Pipe Coupling 5.00 pcs
50mm Ø PVC Pipe Coupling 3.00 pcs
PVC Elbow 90 deg. 100mm Ø 2.00 pcs
PVC Elbow 45 deg. 100mm Ø 3.00 pcs
PVC Wye 100mm Ø 3.00 pcs
PVC Wye 50mm Ø 2.00 pcs
PVC Wye 100m x 50mm Ø 4.00 pcs
PVC Elbow 90 deg. 50mm Ø 4.00 pcs
PVC Elbow 45 deg. 50mm Ø 7.00 pcs
PVC Tee 100mm Ø 4.00 pcs
PVC Sanitary Clean Out 100mm Ø 4.00 pcs
PVC Solvent Cement 3.00 cans
PPR Coupling 3/4" 3.00 pcs
PPR Coupling 1" 2.00 pcs
PPR Tee, 3/4" 4.00 pcs
PPR Tee, 1" 1.00 pcs
PPR Elbow 3/4" Plain 7.00 pcs
PPR Reducer 1" x 3/4" 2.00 pcs
PPR Pipe 1" 1.00 pcs
PPR Pipe 3/4" 2.00 pcs
Gate Valve 1.00 pcs
Teflon Tape 10m 5.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 7.00 days
2 Skilled Laborer 7.00 days
2 Laborer 7.00 days

Equipment

1 One Bagger Mixer 1.00 day
1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-7 Electrical Works

Quantity: 1.00 l.s

Materials:

- 5.5mm2 THHN/THWN Wire 22.00 mtrs
- 3.5mm2 THHN/THWN Wire 60.00 mtrs
- 2.0mm2 THHN/THWN Wire 70.00 mtrs
- T8 18w Louver Type Double Tube Fluorescent Daylight 4.00 pcs
- 14w LED Bulb Daylight with receptacle 5.00 pcs
- Special Purpose Outlet 1.00 pcs
- 2 Gang Switch 3.00 pcs
- 1 Gang Switch 3.00 pcs
- 2 Gang Universal Type Outlet 7.00 pcs
- Junction Box 9.00 pcs
- Flexible Hose 20.00 mtrs
- Plastic Molding 1/2" 8.00 pcs
- 2 HP Split Type ACU 1.00 unit
- AMCO Box 12.00 pcs
- Panel board 6 branches 1.00 unit
- 60Amp Breaker 1.00 pc
- 30Amp Breaker 1.00 pc
- 30Amp Breaker with cover 1.00 pc
- 20 Amp breaker 2.00 pcs
- 15 Amp Breaker 1.00 pcs
- Consumables (5% of Material Cost) 1.00 lot

Labor:

- 1 Construction Foreman 4.00 day
- 4 Skilled Worker 4.00 day
- 3 Laborer 4.00 day

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Improvement of Multi-Purpose Building	For Child Development Center at Brgy. Bukal	1	Lot	1,197,253.73

Other Information

NOTE:

- In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.
- Interested bidders are advised to buy bidding documents at least a day before the opening of bids.

REMINDER:

In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

PREPARATION OF DOCUMENTS

- Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class "A" & Class "B") of documents in separate envelopes: Class "A" documents, containing the legal, technical & financial documents; and Class "B" documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).
- Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.
- Technical Documents must be ring bound with appropriate tabs.
- Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

Created by Noreen A. Ortega

Date Created 20/05/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.