



## Bid Notice Abstract

### Invitation to Bid (ITB)

**Reference Number** 13001615  
**Procuring Entity** MUNICIPALITY OF TIAONG, QUEZON  
**Title** Improvement of Multi-Purpose Building for Child Development Center at Brgy. San Jose, Tiaong, Quezon  
**Area of Delivery** Quezon

<b>Solicitation Number:</b>	I-2026-05-05	<b>Status</b>	<b>Active</b>
<b>Trade Agreement:</b>	Implementing Rules and Regulations	<b>Associated Components</b>	4
<b>Procurement Mode:</b>	Public Bidding	<b>Bid Supplements</b>	0
<b>Classification:</b>	Civil Works	<b>Document Request List</b>	0
<b>Category:</b>	Construction Projects	<b>Date Published</b>	21/05/2026
<b>Approved Budget for the Contract:</b>	PHP 998,276.67	<b>Last Updated / Time</b>	21/05/2026 00:00 AM
<b>Delivery Period:</b>	50 Day/s	<b>Closing Date / Time</b>	28/05/2026 16:00 PM
<b>Client Agency:</b>			
<b>Contact Person:</b>	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851  noreenaortega@gmail.com		

#### Description

B.5 Project Billboard/Signboard  
Quantity: 5.76 sq.m

#### Materials:

Ord. Plywood # 1/2 x 4 x 8 2.00 pcs  
Coco Lumber (2 x 3 x 8) 5.00 pcs  
Tarpaulin (8' x 8') 1.00 unit  
Assorted CWN 1.00 kls

#### Labor:

1 Carpenter 0.50 day  
1 Laborer 0.50 day

B.7 Occupational Safety & Health Program  
Quantity: 1.00 lot

#### Materials:

Safety Helmet 7.00 pcs  
Hand Gloves 7.00 pair  
Safety Shoes 7.00 pair  
Miscellaneous Items 1.00 lot  
(Medicine, Medicine Cabinet, Water, First-Aid Kit)

103 Structure Excavation  
Quantity: 10.40 cu.m

#### Labor:

2 Skilled Worker 2.00 day  
3 Laborer 2.00 day

Equipments:

Minor Tools (10% of Labor Cost)

104 Embankment

Quantity: 2.40 cu.m

Labor:

1 Skilled Worker 1.00 day

1 Laborer 1.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-1 Demolition

Quantity: 1.00 lot

Labor:

3 Skilled Worker 1.00 day

3 Laborer 1.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-2 Reinforced Concrete and Masonry Works

Quantity: 1.00 lot

Materials:

Cement 86.00 pcs

Sand 8.00 cu.m

Gravel 4.00 cu.m

CHB 4" 790.00 pcs

RSB 10mm 82.00 pcs

Ordinary Plywood 1/2" 3.00 pcs

Coco lumber 24.00 bd.ft

Tie Wire 5.00 kgs

Consumables (5% of Materials) 1.00 lot

Labor:

1 Construction Foreman 8.00 day

3 Skilled Worker 8.00 day

3 Laborer 8.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-3 Roofing Works

Quantity: 1.00 lot

Materials:

Long Span Rib Type Colored Roof, Ga. 26 11.00 sq.m.

Angle Bar 2x2x4.5mm 8.00 pcs

C-Purlins (2"x4"x20') 4.00 pcs

C-Purlins (2"x6"x20') 4.00 pcs

Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 4.00 pcs

12" x 1" Plain GI Strap 27.00 pcs

Colored Plain Sheet (4x8) Ga.22 5.00 pcs

Welding Rod 3.00 kgs

Texscrew 200.00 pcs

Cutting Disc 1.00 box

PVC Pipe 3" 4.00 pcs

PVC Elbow 3" 6.00 pcs

Cementitious Water Proofing 3.00 gal

Consumables 1.00 lot

Labor:

1 Construction Foreman 3.00 day

2 Skilled Worker 3.00 day

3 Laborer 3.00 day

Equipments:

1 Welding Machine 4.00 hours

Minor Tools (10% of Labor Cost)

1003 Ceiling Works

Quantity: 73.90 sq.m

Materials:

Hardieflex 4' x 8' 29.00 pcs

Wall Angle 0.6mm x 3m 40.00 pcs  
Carrying Channel 0.8mm x 5m 41.00 pcs  
Double Furring Channel 0.5mm x 5m 37.00 pcs  
Double Furring Clip 230.00 pcs  
Black Teksew 4.00 box  
Perforated Paper Tape 76m/roll 1.00 roll  
Assorted CWN 1.00 kgs  
Latex Paint 6.00 gal  
Paint Brush 2" 3.00 pcs  
Paint Roller 7" with tray 3.00 pcs  
Blind Rivets 4.00 box  
Hardieflex Scoring Knife 2.00 pcs  
Consumables (5% of Materials) 1.00 lot

Labor:

1 Construction Foreman 4.00 day  
3 Skilled Worker 4.00 day  
3 Laborer 4.00 day

1032 Paint Works  
Quantity: 275.30 sq.m

Materials:

Primer Flat Latex 22.00 gal  
Top Coat Latex 25.00 gal  
Gray Metal Primer 1.00 gal  
Paint Brush 4" 2.00 pcs  
Paint Brush 2" 2.00 pcs  
Paint Roller 7" with tray 4.00 pcs  
Sand Paper #100 10.00 meter  
Mesh Tape 5.00 pcs  
Consumables (5% of Materials) 1.00 lot

Labor:

3 Skilled Worker 5.00 day  
3 Laborer 5.00 day

1018 Tile Works  
Quantity: 58.00 sq.m

Materials:

60cm x 60 cm Tiles (Non-skid) 136.00 pcs  
30cm x 30 cm Tiles(Non-skid) 300.00 pcs  
Tile Adhesive 23.00 bags  
Tile Grout 18.00 bags  
Consumables (2% of Materials) 1.00 lot

Labor:

1 Construction Foreman 8.00 day  
3 Skilled Worker 8.00 day  
3 Laborer 8.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-4 Finishing Works  
Quantity: 1.00 lot

Materials:

Playground Set ( Swing and Slide) 1.00 set  
EVA Matting 3.00 set  
Acrylic Lettering 1.00 lot  
Consumables (2% of Materials) 1.00 lot

Labor:

2 Skilled Worker 1.00 day  
2 Laborer 1.00 day

SPL-5 Doors & Windows  
Quantity: 1.00 l.s

Materials:

Glass Door, Swing type, Complete w/ Accessories 6mm (2.1x1.6) 3.36 sq.m  
Flush Hollow Core Door with Door Jamb 1.89 sq.m  
PVC Swing Door with Door Jamb 5.88 sq.m  
Door Locks (Schlage or Equivalent) 5.00 set  
Door Hinge (50mm x 101mm) 20.00 pc  
Consumables 1.00 lot

Labor:

2 Skilled Worker 2.00 day  
2 Laborer 2.00 day

1002(4) Plumbing Fixtures  
Quantity 1.00 I.s.

Materials

"Water Closet inc. fittings & acc. (round)  
american std or equivalent" 3.00 pcs  
"Lavatory inc. fittings & acc. American  
std or equivalent" 3.00 pcs  
Floor Drain 5.00 pcs  
Stainless Sink-Double 1.00 pcs  
Deck Mounted Faucet 3.00 pcs  
Bidet Set 3.00 pcs  
Stainless Wall Faucet 6.00 pcs  
Consumables (5% of Material Cost) 1.00 lot

Labor

2 Skilled Laborer 2.00 days  
2 Laborer 2.00 days

Equipment

1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-6 Water & Sewer Line Works (Including Septic Tank)  
Quantity 1.00 I.s.

Materials

Cement 32.00 pcs  
Sand 2.00 cu.m  
Gravel 3/4 2.00 cu.m  
RSB 12mm 10.00 pcs  
RSB 10mm 24.00 pcs  
CHB 6" 150.00 pcs  
CHB 4" 25.00 pcs  
Liquid Asphalt 2.00 gal  
PVC Pipe, 100mm Ø x 3m, S-100 4.00 pcs  
PVC Pipe, 50mm Ø x 3m, S-100 10.00 pcs  
100mm Ø PVC Pipe Coupling 2.00 pcs  
50mm Ø PVC Pipe Coupling 7.00 pcs  
PVC Elbow 90 deg. 100mm Ø 5.00 pcs  
PVC Elbow 45 deg. 100mm Ø 3.00 pcs  
PVC Wye 100mm Ø 4.00 pcs  
PVC Wye 50mm Ø 7.00 pcs  
PVC Elbow 90 deg. 50mm Ø 17.00 pcs  
PVC Elbow 45 deg. 50mm Ø 3.00 pcs  
PVC Tee 100mm Ø 3.00 pcs  
PVC Tee 50mm Ø 2.00 pcs  
PVC Sanitary Clean Out 100mm Ø 2.00 pcs  
PVC Sanitary Clean Out 50mm Ø 2.00 pcs  
PVC Solvent Cement 4.00 cans  
PPR Coupling 3/4" 4.00 pcs  
PPR Coupling 1" 1.00 pcs  
PPR Tee, 3/4" 14.00 pcs  
PPR Elbow 3/4" Plain 24.00 pcs  
PPR Reducer 1" x 3/4" 2.00 pcs  
PPR Pipe 1" 1.00 pcs  
PPR Pipe 3/4" 6.00 pcs  
Gate Valve 2.00 pcs  
Teflon Tape 10m 5.00 pcs  
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 5.00 days  
2 Skilled Laborer 5.00 days  
2 Laborer 5.00 days

Equipment

1 One Bagger Mixer 1.00 day  
1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-7 Electrical Works  
Quantity: 1.00 I.s

Materials:

1 Gang switch 4.00 pc  
2 Gang switch 2.00 pc  
3 Gang switch 2.00 pcs  
2.0mm<sup>2</sup> wire 1.00 box

3.5mm2 wire 80.00 mtrs  
 Flexible hose 1.00 pcs  
 uPVC Pipe 1/2 9.00 pcs  
 Plastic Molding Pipe 1/2 8.00 pcs  
 Junction Box 14.00 pcs  
 AMCO Box 14.00 pcs  
 2 Gang Universal Type Outlet 6.00 pcs  
 T8 18w Louver Type Double Tube Fluorescent Daylight 6.00 pcs  
 14 led bulb with receptacle 8.00 unit  
 Panel board-6 slot 1.00 pcs  
 15AT Circuit Breaker 1.00 unit  
 20AT Circuit Breaker 2.00 pc  
 60AT Circuit Breaker 1.00 pcs  
 Locknut Bushing 50.00 pcs  
 Consumables (5% of Material Cost) 1.00 lot

**Labor:**

1 Construction Foreman 2.00 day  
 4 Skilled Worker 2.00 day  
 2 Laborer 2.00 day

**Line Items**

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Improvement of Multi-Purpose Building	For Child Development Center at Brgy. San Jose	1	Lot	998,276.67

**Other Information**

**NOTE:**

1. In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.
2. Interested bidders are advised to buy bidding documents at least a day before the opening of bids.

**REMINDER:**

In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

**PREPARATION OF DOCUMENTS**

1. Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class "A" & Class "B") of documents in separate envelopes: Class "A" documents, containing the legal, technical & financial documents; and Class "B" documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).
2. Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.
3. Technical Documents must be ring bound with appropriate tabs.
4. Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

**Created by** Noreen A. Ortega

**Date Created** 20/05/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.