



Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number 13002971
Procuring Entity MUNICIPALITY OF TIAONG, QUEZON
Title Improvement of Multi-Purpose Building for Child Development Center at Sitio Sulukan, Brgy. Anastacia, Tiaong, Quezon (2nd Post)
Area of Delivery Quezon

Solicitation Number:	I-2026-05-09	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	4
Procurement Mode:	Public Bidding	Bid Supplements	0
Classification:	Civil Works	Document Request List	0
Category:	Construction Projects	Date Published	21/05/2026
Approved Budget for the Contract:	PHP 996,816.54	Last Updated / Time	21/05/2026 00:00 AM
Delivery Period:	60 Day/s	Closing Date / Time	28/05/2026 10:00 AM
Client Agency:			
Contact Person:	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851 noreenaortega@gmail.com		

Description

605 Project Billboard/Signboard
Quantity: 5.76 sq.m

Materials:

Ord. Plywood # 1/2 x 4 x 8 2.00 pcs
Coco Lumber (2 x 3 x 8) 5.00 pcs
Tarpaulin (8' x 8') 1.00 unit
Assorted CWN 1.00 kls

Labor:

1 Carpenter 0.50 day
1 Laborer 0.50 day

SPL-1 Occupational Safety & Health Program
Quantity: 1.00 lot

Materials:

Safety Helmet 8.00 pcs
Hand Gloves 8.00 pair
Safety Shoes 8.00 pair
Miscellaneous Items 1.00 lot
(Medicine, Medicine Cabinet, Water, First-Aid Kit)

103 Structure Excavation
Quantity: 5.70 cu.m

Labor:
1 Skilled Worker 1.00 day
3 Laborer 1.00 day

Equipments:
Minor Tools (10% of Labor Cost)

804(1)a Embankment from Structure Excavation
Quantity: 5.00 cu.m

Labor:
1 Construction Foreman 1.00 day
1 Laborer 1.00 day

Equipments:
Minor Tools (10% of Labor Cost)

SPL-2 Demolition and Gate Repair
Quantity: 1.00 lot

Materials:
Welding Rod 5.00 kgs
Cutting Disc 1.00 box

Labor:
2 Skilled Worker 1.00 day
2 Laborer 1.00 day

Equipments:
1 Welding Machine 4.00 hours
Minor Tools (10% of Labor Cost)

SPL-3 Reinforced Concrete and Masonry Works
Quantity: 1.00 lot

Materials:
Cement 43.00 pcs
Sand 4.00 cu.m
Gravel 2.00 cu.m
CHB 4" 355.00 pcs
RSB 10mm 47.00 pcs
Tie Wire 3.00 kgs
Acrylic Lettering 1.00 lot
Consumables (5% of Materials) 1.00 lot

Labor:
1 Construction Foreman 5.00 day
3 Skilled Worker 5.00 day
3 Laborer 5.00 day

Equipments:
Minor Tools (10% of Labor Cost)

SPL-4 Roofing Works
Quantity: 110.25 lot

Materials:
Long Span Rib Type Colored Roof, Ga. 26 116.00 sq.m.
Angle Bar 2x2x4.5mm 43.00 pcs
C-Purlins (2"x4"x20') 49.00 pcs
C-Purlins (2"x6"x20') 8.00 pcs
Channel Bar (2"x4"x20') 1.00 pcs
Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 10.00 pcs
Pre-painted Ridge Roll, x 0.6mm x 2.45 m 5.00 pcs
12" x 1" Plain GI Strap 63.00 pcs
Welding Rod 10.00 kgs
Texscrew 1,200.00 pcs
Cutting Disc 2.00 box
PVC Pipe 3" 8.00 pcs
PVC Elbow 3" 8.00 pcs
Consumables 1.00 lot

Labor:(including the dismantling of existing roof)

1 Construction Foreman 11.00 day

4 Skilled Worker 11.00 day

4 Laborer 11.00 day

Equipments:

Welding Machine 16.00 hours

Minor Tools (10% of Labor Cost)

1003 Ceiling Works

Quantity: 107.75 sq.m

Materials:

Hardieflex 4' x 8' 45.00 pcs

Wall Angle 0.6mm x 3m 51.00 pcs

Carrying Channel 0.8mm x 5m 54.00 pcs

Double Furring Channel 0.5mm x 5m 58.00 pcs

Double Furring Clip 315.00 pcs

Black Tekscew 5.00 box

Perforated Paper Tape 76m/roll 1.00 roll

Assorted CWN 1.00 kgs

Latex Paint 9.00 gal

Paint Brush 2" 2.00 pcs

Paint Roller 7" with tray 2.00 pcs

Blind Rivets 8.00 box

Hardieflex Scoring Knife 2.00 pcs

Consumables (5% of Materials) 1.00 lot

Labor:

1 Construction Foreman 5.00 day

3 Skilled Worker 5.00 day

3 Laborer 5.00 day

1032 Paint Works

Quantity: 226.70 sq.m

Materials:

Primer Flat Latex 20.00 gal

Top Coat Latex 22.00 gal

Gray Metal Primer 4.00 gal

Enamel Paint 4.00 gal

Paint Brush 4" 4.00 pcs

Paint Brush 2" 4.00 pcs

Paint Roller 7" with tray 4.00 pcs

Sand Paper #100 10.00 meter

Mesh Tape 5.00 pcs

Consumables (5% of Materials) 1.00 lot

Labor:

2 Skilled Worker 7.00 day

2 Laborer 7.00 day

1018 Tile Works

Quantity: 56.81 sq.m

Materials:

60cm x 60 cm Tiles (Non-skid) 92.00 pcs

30cm x 30 cm Tiles(Non-skid) 188.00 pcs

Tile Adhesive 12.00 bags

Tile Grout 13.00 bags

Consumables (2% of Materials) 1.00 lot

Labor:

1 Construction Foreman 6.00 day

2 Skilled Worker 6.00 day

2 Laborer 6.00 day

Equipments:

Minor Tools (10% of Labor Cost)

SPL-5 Doors & Windows

Quantity: 1.00 l.s

Materials:

Analok Glass Window with Frame and acc. (1.2x1.6) 0.32 sq.m

Flush Hollow Core Door with Door Jamb 5.67 sq.m
PVC Swing Door with Door Jamb 2.94 sq.m
Door Locks (Schlage or Equivalent) 5.00 set
Door Hinge (50mm x 101mm) 20.00 pc
Consumables 1.00 lot

Labor:

2 Skilled Worker 2.00 day
2 Laborer 2.00 day

1002(4) Plumbing Fixtures
Quantity 1.00 l.s.

Materials

"Water Closet inc. fittings & acc. (round) american
std or equivalent" 2.00 pcs
Floor Drain 3.00 pcs
Stainless Sink-Double 1.00 pcs
Deck Mounted Faucet 5.00 pcs
Bidet Set 2.00 pcs
Stainless Wall Faucet 2.00 pcs
Consumables (5% of Material Cost) 1.00 lot

Labor

2 Skilled Laborer 1.00 days
2 Laborer 1.00 days

Equipment

Minor Tools (10% of Labor Cost) 1.00 lot

SPL-6 Water & Sewer Line Works (Including Septic Tank)
Quantity 1.00 l.s.

Materials

Cement 32.00 pcs
Sand 2.00 cu.m
Gravel 3/4 2.00 cu.m
RSB 12mm 10.00 pcs
RSB 10mm 24.00 pcs
CHB 6" 150.00 pcs
CHB 4" 25.00 pcs
Liquid Asphalt 2.00 gal
PVC Pipe, 100mm Ø x 3m, S-100 5.00 pcs
PVC Pipe, 50mm Ø x 3m, S-100 8.00 pcs
50mm Ø PVC Pipe Coupling 4.00 pcs
PVC Elbow 90 deg. 100mm Ø 3.00 pcs
PVC Wye 100mm Ø 1.00 pcs
PVC Wye 50mm Ø 1.00 pcs
PVC Elbow 90 deg. 50mm Ø 4.00 pcs
PVC Elbow 45 deg. 50mm Ø 2.00 pcs
PVC Tee 100mm Ø 5.00 pcs
PVC Tee 50mm Ø 4.00 pcs
PVC Sanitary Clean Out 100mm Ø 1.00 pcs
PVC Sanitary Clean Out 50mm Ø 1.00 pcs
PVC Solvent Cement 1.00 cans
PPR Coupling 3/4" 3.00 pcs
PPR Coupling 1" 4.00 pcs
PPR Tee, 3/4" 6.00 pcs
PPR Tee, 1" 4.00 pcs
PPR Elbow 3/4" Plain 10.00 pcs
PPR Elbow 1" Plain 6.00 pcs
PPR Reducer 1" x 3/4" 4.00 pcs
PPR Pipe 1" 3.00 pcs
PPR Pipe 3/4" 5.00 pcs
Gate Valve 1.00 pcs
Teflon Tape 10m 3.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor

1 Foreman 5.00 days
2 Skilled Laborer 5.00 days
2 Laborer 5.00 days

Equipment

Minor Tools (10% of Labor Cost)

SPL-7 Electrical Works
Quantity: 1.00 l.s

Materials:

3.5mm² THHN/THWN Wire 75.00 mtrs
2.0mm² THHN/THWN Wire 90.00 mtrs
T8 18w Louver Type Double Tube Fluorescent Daylight 2.00 pcs
14w LED Bulb Daylight with receptacle 5.00 pcs
2 Gang Switch 1.00 pcs
1 Gang Switch 4.00 pcs
2 Gang Universal Type Outlet 3.00 pcs
Junction Box 7.00 pcs
Flexible Hose 30.00 mtrs
Plastic Molding 1/2" 10.00 pcs
AMCO Box 10.00 pcs
Panel board 6 branches 1.00 unit
60Amp Breaker 1.00 pc
20 Amp breaker 2.00 pcs
15 Amp Breaker 1.00 pcs
Consumables (5% of Material Cost) 1.00 lot

Labor:

1 Construction Foreman 2.00 day
2 Skilled Worker 2.00 day
1 Laborer 2.00 day

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Improvement of Multi-Purpose Building	For Child Development Center at Sitio Sulukan, Brgy Anastacia, Tiaong, Quezon	1	Lot	996,816.54

Other Information

NOTE:

1. In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.
2. Interested bidders are advised to buy bidding documents at least a day before the opening of bids.

REMINDER:

In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

PREPARATION OF DOCUMENTS

1. Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class "A" & Class "B") of documents in separate envelopes: Class "A" documents, containing the legal, technical & financial documents; and Class "B" documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).
2. Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.
3. Technical Documents must be ring bound with appropriate tabs.
4. Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

Created by Noreen A. Ortega

Date Created 20/05/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.