



Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number 12968240
Procuring Entity MUNICIPALITY OF TIAONG, QUEZON
Title Improvement of Hanging Bridge at Brgy. San Isidro, Tiaong, Quezon
Area of Delivery Quezon

Solicitation Number:	I-2026-05-02	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	4
Procurement Mode:	Public Bidding	Bid Supplements	0
Classification:	Civil Works	Document Request List	0
Category:	Construction Projects	Date Published	07/05/2026
Approved Budget for the Contract:	PHP 2,983,605.42	Last Updated / Time	07/05/2026 00:00 AM
Delivery Period:	90 Day/s	Closing Date / Time	18/05/2026 15:00 PM
Client Agency:			
Contact Person:	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851 noreenaortega@gmail.com		

Description

605 Project Billboard/Signboard
Quantity: 5.76 sq.m.

Materials:

Ordinary Plywood (1/2" x 4' x 8') pcs. 2
 Coco Lumber (2" x 3" x 12') pcs. 5
 Tarpaulin (8' x 8') unit 1
 Assorted CWN kg. 1

Labor:

1 Carpenter day 0.5
 1 Laborer day 0.5

B.7 Occupational Safety & Health Program
Quantity: 1.00 lot

Materials:

Safety Helmet pcs 15
 Hand Gloves pairs 15
 Safety Shoes pairs 15
 Safety Net & Signages lot 1
 Miscellaneous Items lot 1
 (Medicine, Medicine Cabinet, Water, First Aid Kit)

101 Removal of Structure and Obstructions
Quantity: 1.00 l.s

Labor:

1 Construction Foreman days 7.00
2 Skilled Laborer days 7.00
6 Laborer days 7.00

Equipment:

1 Backhoe with Breaker hour 16.00
Minor Tools (10% of Labor) lot 1.00

103 Structure Excavation
Quantity: 169.42 cu.m

Labor:

1 Construction Foreman day 7.00
3 Laborer day 7.00

Equipment

1 Backhoe (0.80 cu.m) hour 24.00
1 Dump Truck (10 cu.m) hour 24.00
1 Minor Tools (10% of Labor Cost) lot 1.00

104 Embankment
Quantity: 141.00 cu.m

Materials:

Selected Borrow cu.m 186.00

Labor:

1 Construction Foreman days 3.00
3 Unskilled Laborer days 3.00

Equipment:

1 Backhoe hours 14.00
1 Plate Compactor hours 14.00
Minor Tools (10% of Labor Cost) lot 1.00

SPL-1 Masonry and Reinforced Concrete
Quantity: 41.00 cu.m.

Materials:

Cement bags 387.00
Sand cu.m. 26.00
Gravel - 3/4" cu.m. 41.00
RSB 20mmØ x 6.0m RSB pcs 104.00
RSB 16mmØ x 6.0m RSB pcs 87.00
RSB 10mmØ x 6.0m RSB pcs 346.00
CHB 5" pcs 150.00
Good Lumber bd.ft. 1,436.00
Marine Plywood (1/2" x 4' x 8') pcs. 66.00
Assorted CWN kgs. 29.00
G.I. Tie Wire kgs. 21.00

Labor:

1 Construction Foreman days 22
4 Skilled Workers days 22
8 Laborer days 22
Installation & Removal of Formworks/Falseworks
2 Skilled Worker days 13
4 Laborer days 13

Equipment:

2 One Bagger Mixer hours 55
1 Concrete Vibrator hours 55
1 Water Tank hours 6
1 Minor Tools (5% of Labor Cost) lot 1

SPL - 2 Steel & Cable Works
Quantity: 1.00 lot

Materials:

G.I. Pipe Sch. 40 2-1/2" pcs 8.00
G.I. Pipe Sch. 40 2" pcs 40.00

Checkered Plate, 1/8" x 4' x 8' sheets 18.00
 MS Plate, 4" x 8" x 1/4" sheets 94.00
 Cable Rope, 1 1/4" dia. (Main Rope) m 126.00
 Cable Rope, 1/2" dia. (Suspender) m 292.00
 Cable Clamp, 1 1/4" pcs 24.00
 Cable Clamp, 1/2" pcs 150.00
 Cable Thimble, 1" pcs 8.00
 Steel Cable Shackle Buckle, Heavy Duty pcs 24.00
 Steel Cable Turnbuckle pcs 8.00
 Anchor Hook, 32mm dia. pcs 4.00
 Anchor Bolt, 32mm dia. pcs 8.00
 Cyclone Wire Ga. 10 In.m 84.00
 10mm dia. Steel Rod Round Bar pcs 56.00
 Welding Rod kgs 130.00
 Consumables lot 1.00

Labor:

1 Construction Foreman days 21
 6 Skilled Worker days 21
 12 Laborer days 21

Equipment

1 Welding Machine hours 50.00
 1 Cutting Outfit hours 50.00
 1 Cable Tightening Machine hours 33.00
 1 Minor Tools (10% of Labor Cost) lot 1.00

1032 Painting Works

Quantity: 204.00 sq.m

Materials:

Concrete Neutralizer gals 5.00
 Concrete Sealer/Primer gals 9.00
 Patching Compound gals 11.00
 Semi Gloss Latex gals 17.00
 Red Oxide Primer gals 9.00
 Flat Wall Enamel gals 21.00
 Paint Thinner gals 13.00
 Consumables (5% of Materials) lot 1.00

Labor:

1 Construction Foreman days 8
 2 Skilled Worker - Painter days 8
 2 Laborer days 8

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Improvement of Hanging Bridge	Brgy. San Isidro, Tiaong, Quezon	42	Meter	2,983,605.42

Other Information

NOTE:

- In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.
- Interested bidders are advised to buy bidding documents at least a day before the opening of bids.

REMINDER:

In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

PREPARATION OF DOCUMENTS

- Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class "A" & Class "B") of documents in separate envelopes: Class "A" documents, containing the legal, technical & financial documents; and Class "B" documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).
- Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.
- Technical Documents must be ring bound with appropriate tabs.

4. Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

Created by Noreen A. Ortega

Date Created 06/05/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.