Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number	13277146
Procuring Entity	MUNICIPALITY OF TIAONG, QUEZON
Title	Completion/Upgrading/Repair of Tiaong Super Health Center at Brgy. Ayusan II
Area of Delivery	Quezon

Solicitation Number:	I-2026-10-01
Trade Agreement:	Implementing Rules and Regulations
Procurement Mode:	Public Bidding
Classification:	Civil Works
Category:	Construction Projects
Approved Budget for the Contract:	PHP 4,899,772.86
Delivery Period:	150 Day/s
Client Agency:	
Contact Person:	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851 noreenaortega@gmail.com

Status	**Active**
Associated Components	3
Bid Supplements	0
Document Request List	4
Date Published	08/10/2026
Last Updated / Time	08/10/2026 00:00 AM
Closing Date / Time	27/10/2026 14:00 PM

Description

B.5 Project Billboard/Signboard
Quantity: 1.00 each

Materials
Ordinary Plywood (1/2" x 4' x 8') 2.00 pcs
Coco Lumber (2" x 3" x 12') 5.00 pcs
Tarpaulin (8' x 8') 1.00 unit
Assorted CWN 1.00 kg

Labor
1 Carpenter 0.50 days
2 Laborer 0.50 days

B.7 Construction Safety and Health
Quantity: 1.00 lot

Materials
Safety Helmet 34.00 pcs
Hand Gloves 34.00 pairs
Safety Shoes 34.00 pairs
Misc (Medicine, Medicine Cabinet, Water, First Aid Kit) 1.00 lot

803(1)a Structure Excavation, Common Soil
Quantity: 65.00 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment
1 Backhoe (0.80 cu.m) 2.00 hour
2 Dump Truck (12 cu.yd) 2.00 hour

804(1)a Embankment from Structure Excavation
Quantity: 43.00 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment
1 Backhoe (0.80 cu.m) 2.00 hour
1 Plate Compactor 4.00 hour

804(2)a Embankment from Borrow
Quantity: 156.00 cu.m

Materials
Common Borrow 195.00 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment
1 Backhoe (0.80 cu.m) 2.00 hour
1 Plate Compactor 8.00 hour

804(7) Gravel Fill
Quantity 29.00 cu.m

Materials
Gravel Fill 31.00 cu.m

Labor
1 Foreman 2.00 days
3 Laborer 2.00 days

Equipment
1 Plate Compactor 12.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

900(1)d Structural Concrete (4000 psi, Class A, 28 days)
Quantity 64.00 cu.m

Materials
Ready Mix Concrete 4000Psi @ 28 Days 70.00 cu.m

Labor
1 Foreman 3.00 days
2 Skilled Laborer 3.00 days
6 Laborer 3.00 days

Equipment
2 Concrete Vibrator 17.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

902(1)a1 Reinforcing Steel (Deformed) Grade 40
Quantity 6,809.16 kg

Materials
Reinforcing Steel Bars Deformed Grade 40 7,150.00 kg
GI Tie Wire #16 108.00 kg

Labor
1 Foreman 7.00 days
3 Skilled Laborer 7.00 days
8 Laborer 7.00 days

Equipment
1 Bar Cutter 26.00 hour
1 Bar Bender 26.00 hour
Minor Tools (10% of Labor Cost) 1.00 lot

903(2) Formworks and Falseworks
Quantity 288.08 sq.m

Materials
Phenolic Board - 1.22m x 2.44m x 18mm 25.00 pc
Good Lumber 681.00 bd.ft

Labor
1 Foreman 5.00 days
2 Skilled Laborer 5.00 days
4 Laborer 5.00 days
Stripping
1 Foreman 2.00 days
3 Laborer 2.00 days

Equipment
40 H-Frame 1.7 m x 1.2m, set 20.00 hrs
2pcs H-frames
4pcs diagonal cross braces
4pcs Horizontal cross braces
8pcs joint pins
62 Shoring Jack,3.8 m full extension 20.00 hrs
80 Adj. U-Head Jack, 0.60m 20.00 hrs
80 Adj. Base Jack, 0.60m 20.00 hrs
62 1-1/2" GI Pipe x 6.0 m 20.00 hrs
16 1-1/2" GI Pipe x 3.0 m 20.00 hrs
32 1-1/2" GI Pipe x 4.0 m 20.00 hrs
216 1-1/2" GI Pipe x 1.0 m 20.00 hrs
278 Tie Rod x 0.60m 20.00 hrs
558 Round Wing Not 20.00 hrs

1000(1) Soil Poisoning
Quantity 35.00 liter

Materials
Soil Poisoning 35.00 lit

Labor
1 Foreman 1.00 days
1 Laborer 1.00 days

Equipment
Minor Tools (10% of Labor Cost) 1.00 lot

1046(2)a1 CHB Non-Load Bearing (including Reinforcing Steel), 100mm
Quantity 122.16 sq.m

Materials
CHB Ordinary (101mm x 203mm x 406mm) 1,589.00 pcs
Portland Cement 65.00 bag
Sand 5.00 cu.m
Reinforcing Steel Bars Deformed Grade 40 396.00 kg
GI Tie Wire #16 7.00 kg

Labor
1 Foreman 5.00 days
2 Skilled Laborer 5.00 days
3 Laborer 5.00 days

Equipment
1 One Bagger Mixer 39.00 hour
Minor Tools (10% of Labor Cost) 1.00 lot

1046(2)a2 CHB Non-Load Bearing (including Reinforcing Steel), 150mm
Quantity 208.00 sq.m

Materials
CHB Ordinary (150mm x 230mm x 406mm) 2,704.00 pcs
Portland Cement 111.00 bag
Sand 9.00 cu.m
Reinforcing Steel Bars Deformed Grade 40 774.00 kg
GI Tie Wire #16 11.00 kg

Labor
1 Foreman 9.00 days
2 Skilled Laborer 9.00 days
3 Laborer 9.00 days

Equipment
1 One Bagger Mixer 66.00 hour
Minor Tools (10% of Labor Cost) 1.00 lot

1010(2)a Doors, Flush
Quantity 33.26 sq.m.

Materials
Flush Hollow Core Door with Door Jamb, Kickplate, 6mm glass 10.54 sq.m
Flush Hollow Core Door with Door Jamb, Kickplate 18.06 sq.m
Glass Door Panel 4.66 sq.m
Door Locks (Schlage or Equivalent) 13.00 set
Pull Handle 2.00 set
Door Hinge (50mm x 101mm) 56.00 pc

Labor
1 Foreman 5.00 days
1 Skilled Laborer 5.00 days
1 Laborer 5.00 days

1008(1)c Aluminum Glass Window
Quantity 18.54 sq.m

Materials
Aluminum framed Glass Window 18.54 sq.m

Labor
1 Foreman 2.00 days
1 Skilled Laborer 2.00 days
1 Laborer 2.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1027(1) Cement Plaster Finish
Quantity 687.00 sq.m

Materials
Portland Cement 227.00 bag
Sand 19.00 cu.m

Labor
1 Foreman 10.00 days
2 Skilled Laborer 10.00 days
2 Laborer 10.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1003(1)a1 Ceiling (4.5mm, Metal Frame, Fiber Cement Board)
Quantity 233.00 sq.m

Materials
15mm thick Armstrong acoustic ceiling/Ficem board 86.00 pcs
Metal Furring 3m length 264.00 pcs
Carrying Channels 84.00 pcs
Hanger Bars/Rod 35.00 pcs

Channel clip 1,398.00 pcs
Wall Angle 77.00 pcs
Rivets 3,262.00 pcs
1" Metal Screw 932.00 pcs
Perforated Paper Tape 76m/roll 10.00 roll
Hardie Putty 82.00 kgs
Acrylic Latex Paint 22.00 gal
Paint Brush 2" 10.00 pcs
Paint Roller 7" 10.00 pcs

Labor
1 Foreman 12.00 days
3 Skilled Laborer 12.00 days
4 Laborer 12.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1018(1) Tile Works
Quantity 62.00 sq.m

Materials
30cm x 60 cm Tiles 306.00 pcs
30cm x 30 cm Tiles 148.00 pcs
Tile Adhesive 13.00 bags
Tile Grout 16.00 bags
Consumables (2% of Material Cost) 1.00 lot

Labor
1 Foreman 6.00 days
3 Skilled Laborer 6.00 days
3 Laborer 6.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1032 Painting Works
Quantity 621.00 sq.m

Materials
Concrete Neutralizer 13.00 gal
Concrete Sealer/Primer 25.00 gal
Patching Compound 42.00 gal
Semi-Gloss Latex (2 coats only) 60.00 gal
Acrylic Water-Based Epoxy 15.00 gal
Red Oxide Primer 15.00 gal
Paint Brush # 3 5.00 pcs
Paint Roller 7" with tray 4.00 pcs
Consumables (3% of Materials Cost) 1.00 lot

Labor
1 Foreman 15.00 days
2 Skilled Laborer 15.00 days
1 Laborer 15.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1014(1)b2 Prepainted Metal Sheets (above 0.427mm) Rib Type Long Span
Quantity 250.00 sq.m.

Materials
Long Span Rib Type Colored Roof, Ga. 26 263.00 sq.m.
Reflective Insulation, 5 mm thk 250.00 sq.m
Tekscrew 2,500.00 pcs
Consumables (2% of Materials Cost) 1.00 lot

Labor
1 Foreman 16.00 days
2 Skilled Laborer 16.00 days
2 Laborer 16.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(7) Structural Steel (TRUSS)
Quantity 2,829.00 kg

Materials
Structural Steel Truss 2,870.00 kg
Acetylene 32.00 kg
Oxygen 64.00 kg
Welding Rod 58.00 kg
Consumables (1% of Materials Cost) 1.00 lot

Labor
1 Foreman 7.00 days
2 Skilled Laborer 7.00 days
2 Laborer 7.00 days
Erection
2 Skilled Laborer 4.00 days
3 Laborer 4.00 days

Equipment
1 Welding Machine, Electric Driven/DC Output, 500 Amp 26.00 hours
1 Cutting Outfit 9.00 hours

1 Grinding Machine and Accessories 28.00 hours
1 Cargo/Service Truck, 2-5 mt, 160 hp 4.00 hours
1 Boom Truck, NXG1160D3ZAL1X, 197 hp 6.00 hours
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(8)b Structural Steel (Purlins)
Quantity 749.00 kg

Materials
Structural Steel Purlins 432.00 kg
Welding Rod 15.00 kg
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 2.00 days
3 Skilled Laborer 2.00 days
3 Laborer 2.00 days

Equipment
2 Welding Machine, Electric Driven/DC Output, 500 Amp 4.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(5) Metal Structure Accessories
Quantity 306.15 kg

Materials
Steel Plates 306.15 kg
Bolts and Rods 56.00 ea
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 2.00 days
2 Skilled Laborer 2.00 days
2 Laborer 2.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)b Fabricated Metal Roofing Accessory (Flashing)
Quantity 85.00 l.m

Materials
Pre-painted flashing, Ga.24 (0.701mm) x 2.44mm 90.00 m
Blind Rivets 1,615.00 pc
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
1 Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)c Fabricated Metal Roofing Accessory (Gutter, Ga. 24)
Quantity 30.70 l.m

Materials
Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 31.00 m
12" x 1" Plain GI Strap 93.00 pc
Blind Rivets 492.00 pc
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
1 Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-2 Finishing Works
Quantity 1.00 l.s.

Materials
GI Pipe 1 1/2'' 16.00 pc
Welding Rod 2.00 kg
Consumables (4% of Materials Cost) 1.00 lot

Labor
1 Foreman 3.00 days
1 Skilled Laborer 3.00 days
2 Laborer 3.00 days

Equipment
1 Welding Machine, Electric Driven/DC Output, 500 Amp 12.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(8) Sewer Line Works & Vents
Quantity 1.00 l.s.

Materials
PVC Pipe, 100mm Ø x 3m, S-100 14.00 pcs
PVC Pipe, 50mm Ø x 3m, S-100 24.00 pcs
PVC Elbow 90 deg. 100mm Ø 4.00 pcs
PVC Elbow 90 deg. 50mm Ø 11.00 pcs
PVC Elbow 45 deg. 50mm Ø 34.00 pcs

PVC Tee 100mm Ø 4.00 pcs
PVC Tee 50mm Ø 14.00 pcs
100mm Ø PVC Pipe Coupling 10.00 pcs
50mm Ø PVC Pipe Coupling 3.00 pcs
PVC Sanitary Clean Out 100mm Ø 3.00 pcs
PVC Solvent Cement 20.00 cans
Consumables (5% of Materials) 1.00 lot

Labor
1 Foreman 4.00 days
1 Skilled Laborer 4.00 days
2 Laborer 4.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(24) Cold Water lines
Quantity 1.00 l.s.

Materials
PPR Coupling 3/4" 5.00 pcs
PPR Coupling 1" 6.00 pcs
PPR Tee, 3/4" 4.00 pcs
PPR Tee, 1" 10.00 pcs
PPR Elbow 3/4" Plain 38.00 pcs
PPR Elbow 1" Plain 3.00 pcs
PPR Reducer 1" x 3/4" 10.00 pcs
PPR Welding Machine 1.00 pcs
Isolation Valve 11.00 pcs
PPR Pipe 1'' 10.00 pcs
PPR Pipe 3/4'' 8.00 pcs
Gate Valve 1.00 pcs
Check Valve 1.00 pcs
Water Meter 1.00 pcs
Teflon Tape 10m 20.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor
1 Foreman 2.00 days
3 Skilled Laborer 2.00 days
3 Laborer 2.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(9) Storm Drainage and Downspout
Quantity 1.00 l.s.

Materials
100mm Ø PVC DS 8.00 pcs
100mm Ø PVC Pipe 90deg elbow 8.00 pcs
100mm Ø PVC Pipe Coupling 6.00 pcs
Roof Drain (Dome Type Strainer) 4.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
2 Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(4) Plumbing Fixtures
Quantity 1.00 l.s.

Materials
Water Closet inc. fittings & acc. (round) american std or equivalent 4.00 pcs
Lavatory inc. fittings & acc. American std or equivalent 4.00 pcs
Floor Drain 10.00 pcs
Stainless Sink–Double 5.00 pcs
Deck Mounted Faucet 5.00 pcs
Brass Wall Faucet 3.00 pcs
Urinal 1.00 pcs
Consumables (3% of Material Cost) 1.00 lot

Labor
1 Foreman 6.00 days
2 Skilled Laborer 6.00 days
2 Laborer 6.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(5)b Catch Basin (CHB)
Quantity 4.00 each

Materials
Portland Cement 8.00 bags
Sand 1.00 cu.m
Gravel 3/4 1.00 cu.m
RSB Grade 40, 10 mm 45.00 kgs
#16 Galvanized Iron Wire 1.00 kgs
Metal Grating 19.00 kgs
CHB, Non Load Bearing, 4" 52.00 pcs

Labor

1 Foreman 2.00 days
1 Skilled Laborer 2.00 days
1 Laborer 2.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-3 Electrical Works
Quantity 1.00 l.s.

Materials
100A, 2P, 230V MCCB 1.00 unit
22mm2 THHN/THWN Wire 36.00 mtrs
8.0mm2 THHN/THWN Wire 70.00 mtrs
5.5mm2 THHN/THWN Wire 1.00 box
3.5mm2 THHN/THWN Wire 1.50 box
2.0mm2 THHN/THWN Wire 2.50 box
12w LED Round Recessed Pinlight Daylight 24.00 pcs
18w LED SQUARE Recessed Pinlight Daylight 24.00 pcs
Special Purpose Outlet 4.00 pcs
2 Gang Universal Type Outlet 24.00 pcs
2 Gang Switch 2.00 pcs
3 Gang Switch 1.00 pcs
1 Gang Switch 12.00 pcs
Junction Box 50.00 pcs
UPVC Pipe 2" 6.00 pcs
UPVC Pipe 1/2" 120.00 pcs
PVC Locknot with bushing 1/2" 50.00 pcs
Dyna Bolt 3/8 6.00 pcs
Utility Box 50.00 pcs
Panel board 14 branches with provision for PP 1.00 unit
30Amp Breaker 7.00 pcs
20 Amp breaker 2.00 pcs
40 Amp Breaker 2.00 pcs
Consumables (3% of Material Cost) 1.00 lot

Labor
1 Foreman 7.00 days
4 Skilled Laborer 7.00 days
2 Laborer 7.00 days

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Completion/Upgrading/Repair of Super Health Center	Completion/Upgrading/Repair of Tiaong Super Health Center at Brgy. Ayusan II	1	Lot	4,899,772.86

Pre-bid Conference

Date	Time	Venue
15/10/2026	4:00:00 PM	Office of the Bids and Awards Committee

Other Information
NOTE:

1. In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.

2. Interested bidders are advised to purchase the bidding documents no later than one (1) day before the scheduled opening of bids.

REMINDER:
In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

PREPARATION OF DOCUMENTS
1. Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class “A” & Class “B”) of documents in separate envelopes: Class “A” documents, containing the legal, technical & financial documents; and Class “B” documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).

2. Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.

3. Technical Documents must be ring bound with appropriate tabs.

4. Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

Created by	Noreen A. Ortega
Date Created	07/10/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.

© 2004-2026 DBM Procurement Service. All rights reserved.