Bid Notice Abstract

Invitation to Bid (ITB)

Reference Number	13289154
Procuring Entity	MUNICIPALITY OF TIAONG, QUEZON
Title	Construction of Two-Storey School Building at San Isidro Elementary School, Brgy. San Isidro, Tiaong, Quezon
Area of Delivery	Quezon

Solicitation Number:	I-2026-10-06
Trade Agreement:	Implementing Rules and Regulations
Procurement Mode:	Public Bidding
Classification:	Civil Works
Category:	Construction Projects
Approved Budget for the Contract:	PHP 9,993,072.69
Delivery Period:	150 Day/s
Client Agency:	
Contact Person:	Noreen A. Ortega Executive Assistant I Poblacion Tiaong Quezon Philippines 4325 63-063-09176252851 noreenaortega@gmail.com

Status	**Active**
Associated Components	4
Bid Supplements	0
Document Request List	5
Date Published	15/10/2026
Last Updated / Time	15/10/2026 00:00 AM
Closing Date / Time	06/11/2026 15:00 PM

Description

B.5 Project Billboard/Signboard
Quantity: 1.00 each

Materials:
Ordinary Plywood (1/2" x 4' x 8') 2.00 pcs.
Coco Lumber (2" x 3" x 12') 5.00 pcs.
Tarpaulin (8' x 8') 1.00 unit
Assorted CWN 1.00 kg.

Labor:
1 Carpenter 0.50 day
2 Laborer 0.50 day

B.7 Construction Safety and Health
Quantity: 1.00 l.s.

Materials
Safety Helmet 30.00 pc(s)
Hand Gloves 30.00 pair(s)
Safety Shoes 30.00 pair(s)
Safety Vest 30.00 pc(s)
Rain Coats 30.00 pc(s)
Dust Mask 30.00 pc(s)
Eye Goggles 30.00 pc(s)
Misc (Medicine, Medicine Cabinet, Water, First Aid Kit) 1.00 lot

801 Removal of Structures and Obstructions
Quantity: 1.00 l.s.

Labor
1 Foreman 5.00 days
8 Laborer 5.00 days

Equipment
1 Backhoe (0.80 cu.m) 4.00 hour
1 Dump Truck (12 cu.yd) 4.00 hour
1 Minor Tools 1.00 l.s

803(1)a Structure Excavation, Common Soil
Quantity: 104.00 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment

1 Backhoe (0.80 cu.m) 6.00 hour
2 Dump Truck (12 cu.yd) 6.00 hour

804(1)a Embankment from Structure Excavation
Quantity: 78.00 cu.m

Labor
1 Foreman 1.00 days
3 Laborer 1.00 days

Equipment
1 Backhoe (0.80 cu.m) 8.00 hour
1 Plate Compactor 8.00 hour

804(7) Gravel Fill
Quantity 23.00 cu.m

Materials
Gravel Fill 25.00 cu.m

Labor
1 Foreman 3.00 days
3 Laborer 3.00 days

Equipment
1 Plate Compactor 9.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

900(1)c Structural Concrete (3000 psi, Class A, 28 days)
Quantity 17.00 cu.m

Materials
Ready Mix Concrete 3000Psi @ 28 Days 18.00 cu.m

Labor
1 Foreman 2.00 days
2 Skilled Laborer 2.00 days
6 Laborer 2.00 days

Equipment
2 Concrete Vibrator 5.00 hour
1 Pumpcrete 2.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

900(1)d Structural Concrete (4000 psi, Class A, 28 days)
Quantity 81.25 cu.m

Materials
Ready Mix Concrete 4000Psi @ 28 Days 85.00 cu.m

Labor
1 Foreman 8.00 days
2 Skilled Laborer 8.00 days
6 Laborer 8.00 days

Equipment
2 Concrete Vibrator 26.00 hour
1 Pumpcrete 15.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

902(1)a1 Reinforcing Steel (Deformed) Grade 40
Quantity 7,232.10 kg

Materials
Reinforcing Steel Bars Deformed Grade 40 7,233.00 kg
GI Tie Wire #16 109.00 kg

Labor
1 Foreman 8.00 days
3 Skilled Laborer 8.00 days
12 Laborer 8.00 days

Equipment
1 Bar Cutter 29.00 hour
1 Bar Bender 29.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

902(1)a2 Reinforcing Steel (Deformed) Grade 60
Quantity 9,518.17 kg

Materials
Reinforcing Steel Bars Deformed Grade 60 9,519.00 kg
GI Tie Wire #16 143.00 kg

Labor
1 Foreman 11.00 days
3 Skilled Laborer 11.00 days
12 Laborer 11.00 days

Equipment
1 Bar Cutter 38.00 hour
1 Bar Bender 38.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

903(2) Formworks and Falseworks
Quantity 634.00 sq.m

Materials
Phenolic Board - 1.22m x 2.44m x 18mm 55.00 pc
Good Lumber 999.00 bd.ft
Consumables (1% of Materials Cost) 1.00 lot

Labor
1 Foreman 18.00 days
4 Skilled Laborer 18.00 days
6 Laborer 18.00 days
Stripping
6 Laborer 10.00 days

Equipment
40 H-Frame 1.7 m x 1.2m, set 43.00 hrs
2pcs H-frames
4pcs diagonal cross braces
4pcs Horizontal cross braces
8pcs joint pins
62 Shoring Jack,3.8 m full extension 43.00 hrs
80 Adj. U-Head Jack, 0.60m 43.00 hrs
80 Adj. Base Jack, 0.60m 43.00 hrs
62 1-1/2" GI Pipe x 6.0 m 43.00 hrs
16 1-1/2" GI Pipe x 3.0 m 43.00 hrs
32 1-1/2" GI Pipe x 4.0 m 43.00 hrs
216 1-1/2" GI Pipe x 1.0 m 43.00 hrs
278 Tie Rod x 0.60m 43.00 hrs
558 Round Wing Not 43.00 hrs

1000(1) Soil Poisoning
Quantity 91.00 liter

Materials
Soil Poisoning 91.00 lit

Labor
1 Foreman 3.00 days
1 Skilled Laborer 3.00 days
1 Laborer 3.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1046(2)a1 CHB Non-Load Bearing (including Reinforcing Steel), 100mm
Quantity 123.00 sq.m

Materials
CHB Ordinary (101mm x 203mm x 406mm) 1,599.00 pcs
Portland Cement 65.00 bag
Sand 6.00 cu.m
Reinforcing Steel Bars Deformed Grade 40 399.00 kg
GI Tie Wire #16 7.00 kg

Labor
1 Foreman 5.00 days
2 Skilled Laborer 5.00 days
3 Laborer 5.00 days

Equipment
1 One Bagger Mixer 36.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1046(2)a2 CHB Non-Load Bearing (including Reinforcing Steel), 150mm
Quantity 244.00 sq.m.

Materials
CHB Ordinary (150mm x 230mm x 406mm) 3,172.00 pcs
Portland Cement 366.00 bag
Sand 11.00 cu.m
Reinforcing Steel Bars Deformed Grade 40 791.00 kg
GI Tie Wire #16 13.00 kg

Labor
1 Foreman 10.00 days
2 Skilled Laborer 10.00 days
3 Laborer 10.00 days

Equipment
1 One Bagger Mixer 74.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1010 Doors
Quantity 23.00 sq.m.

Materials
Panel Door 8.00 sq.m
Flush Hollow Core Door 15.00 sq.m
Door Frames (Jambs, Sills, Head, Transoms and Mullions) 12.00 set
Door Locks (Schlage or Equivalent) 12.00 set
Door Hinge (50mm x 101mm) 48.00 pc
Consumables (5% of Material Cost) 1.00 lot

Labor
1 Foreman 8.00 days
3 Skilled Laborer 8.00 days
3 Laborer 8.00 days

1008(1)c Aluminum Glass Window (Awning Type)

Quantity 32.00 sq.m

Materials
Aluminum framed Glass Window (Awning Type) 32.00 sq.m
Consumables (3% of Material Cost) 1.00 lot

Labor
1 Foreman 6.00 days
1 Skilled Laborer 6.00 days
2 Laborer 6.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1027(1) Cement Plaster Finish
Quantity 734 sq.m

Materials
Portland Cement 243.00 bag
Sand 20.00 cu.m

Labor
1 Foreman 10.00 days
2 Skilled Laborer 10.00 days
3 Laborer 10.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1003(1)a1 Ceiling (4.5mm, Metal Frame, Fiber Cement Board)
Quantity 247 sq.m

Materials
4.5 mm Fiber Cement Board 91.00 pcs
Metal Furring (3/4" x 2" x 16', 0.5 mm thk) 280.00 pcs
Carrying Channel (1" x 2" x 16',0.6 mm thk) 89.00 pcs
Hanger Bars/Rod 247.00 pcs
Channel clip 1,482.00 pcs
Wall Angle, Ga.26 (1" x 1"x 10', 0.4 mm thk) 59.00 pcs
Rivets (5/32" x 3/8") 3,458.00 pcs
1" Metal Screw 988.00 pcs

Labor
1 Foreman 21.00 days
1 Skilled Laborer 21.00 days
2 Laborer 21.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1003(11) Fascia Board (19mm, Fiber Cement Board)
Quantity 47 l.m.

Materials
2-12 mm x 300mm Fiber Cement Board 47.00 m
1" Metal Screws 564.00 pc
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1003 (17) Carpentry and Joinery Works
Quantity 1.00 l.s

Materials
Marine Plywood (1/4'' x 4' x 8') 4.00 pc
Good Lumber 50.00 bd-ft
CWN, Assorted 3.00 kg
Concrete Nail, Assorted 1.00 kg
Solvent-Based Primer 0.50 gal
Blackboard Paint 3.00 L
Paint Thinner 1.00 gal
Door Handle Lever Type 11.00 set
Consumables 1.00 lot

Labor
1 Foreman 3.00 days
1 Skilled Laborer 3.00 days
1 Laborer 3.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1018(1) Glazed Tiles and Trims
Quantity 219 sq.m

Materials
Ceramic Glazed Tiles 230.00 sq.m
Portland Cement 72.00 bags
Sand 6.00 cu.m
Tile Grout 27.00 bags
Tile Adhesive 31.00 bags
Consumables 1.00 lot

Labor
1 Foreman 11.00 days
5 Skilled Laborer 11.00 days
5 Laborer 11.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1018(2) Unglazed Tiles
Quantity 43 sq.m

Materials
Ceramic Unglazed Tiles 46.00 sq.m
Portland Cement 14.00 bags
Sand 2.00 cu.m
Tile Grout 6.00 bags
Consumables (2% of Material Cost) 1.00 lot

Labor
1 Foreman 3.00 days
5 Skilled Laborer 3.00 days
5 Laborer 3.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1021(1)c Cement Floor Finish (with Floor Hardener)
Quantity 12.00 sq.m

Materials
Cement 9.00 sq.m
Sand 1.00 sq.m
Floor Hardener 1.00 bag

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
2 Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1021(1)a Cement Floor Finish (Plain)
Quantity 70.00 sq.m

Materials
Cement 51.00 sq.m
Sand 4.00 sq.m

Labor
1 Foreman 2.00 days
1 Skilled Laborer 2.00 days
3 Laborer 2.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

SPL-I Finishing Works
Quantity 1.00 lot

Materials
Decorative Red Brick Wall 1.00 lot
Stainless Lettering 1.00 set
Consumables (5% of Material Cost) 1.00 lot

Labor
1 Foreman 5.00 days
1 Skilled Laborer 5.00 days
3 Laborer 5.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1032(1)a Painting Works (Masonry/Concrete)
Quantity 915 sq.m

Materials
Concrete Neutralizer 19.00 gal
Concrete Sealer/Primer 37.00 gal
Patching Compound 46.00 gal
Semi-Gloss Latex (2 coats only) 74.00 gal
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 29.00 days
2 Skilled Laborer 29.00 days
1 Laborer 29.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1032(1)b Painting Works (Wood)
Quantity 16.00 sq.m

Materials
Glazzing Putty 1.00 gal

Flat Wall Paint Enamel 1.00 gal
Enamel Quick Dry 1.00 gal
Paint Thinner 4.00 liter
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
1 Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1032(1)c Painting Works (Steel)
Quantity 254 sq.m

Materials
Red Oxide Primer 11.00 gal
Flat Wall Enamel 26.00 gal
Paint Thinner 64.00 liter
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 9.00 days
2 Skilled Laborer 9.00 days
1 Laborer 9.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1014(1)b2 Prepainted Metal Sheets (above 0.427mm) Rib Type Long Span
Quantity 191 sq.m.

Materials
Prepainted Metal Sheets (above 0.427 mm, Rib Type, Long Span) 201.00 sq.m.

Tekscrew w/ J-bolt with washers 1,910.00 pcs
Consumables (3% of Materials Cost) 1.00 lot

Labor
1 Foreman 9.00 days
1 Skilled Laborer 9.00 days
2 Laborer 9.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(7) Structural Steel
Quantity 1,454.00 kg.

Materials
Structural Steel Truss 1,454.00 kg
Acetylene 16.00 kg
Oxygen 32.00 kg
Welding Rod 30.00 kg
Consumables Materials (3% of Matl. Cost) 1.00 lot

Labor
1 Foreman 4.00 days
2 Skilled Laborer 4.00 days
2 Laborer 4.00 days
Erection
1 Skilled Laborer 3.00 days
2 Laborer 3.00 days

Equipment
1 Welding Machine, Electric Driven/DC Output, 500 Amp 13.00 hours
1 Cutting Outfit 5.00 hours
1 Truck-Mounted Crane, Std Lattice Boom 9.00 hours
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(8)b Structural Steel (Purlins)
Quantity 1,400.00 kg

Materials
Structural Steel Purlins 1,414.00 kg
Welding Rod 28.00 kg
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 4.00 days
2 Skilled Laborer 4.00 days
4 Laborer 4.00 days

Equipment
2 Welding Machine, Electric Driven/DC Output, 500 Amp 16.00 hour
1 Minor Tools (10% of Labor Cost) 1.00 lot

1047(5) Metal Structure Accessories
Quantity 419.00 kg

Materials
Steel Plates 163.00 kg
Sagrod with nuts & Bolts 129.00 kg
Cross Bracing 127.00 kg
16mm Ø turn buckles 12.00 pc
Bolts and Rods 18.00 ea

Consumables (1% of Materials Cost) 1.00 lot

Labor
1 Foreman 5.00 days
2 Skilled Laborer 5.00 days
2 Laborer 5.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1051 (1) Railing
Quantity 1.00 l.s

Materials
Stainless Steel Pipe, Sch 40. (2" | 50 mm dia) 10.00 pc
Welding Rod 20.00 kg
Stainless Steel Pipe, Sch 40. (2" | 38 mm dia.) 17.00 pc
50 x 100 x 5 mm Rectangular Hollow bar 5.00 pc
50 x 50 x 2 mm Rectangular Hollow bar 18.00 pc
Checkered Plate 6mm (Flooring) 10.00 set
Consumables 1.00 lot

Labor
1 Foreman 9.00 days
5 Skilled Laborer 9.00 days
5 Laborer 9.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)b Fabricated Metal Roofing Accessory (Flashing, Ga. 26)
Quantity 51.50 l.m

Materials
Pre-painted flashing, Ga.26 (0.551mm) x 2.44mm 55.00 m
Blind Rivets 979.00 pc
Consumables (3% of Materials Cost) 1.00 lot

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
1 Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1013(2)c Fabricated Metal Roofing Accessory (Gutter, Ga. 24)
Quantity 47.00 l.m

Materials
Pre-painted Gutter, Ga. 24 (0.701 mm) X 2.44 m 47.00 m
12" x 1" Plain GI Strap 141.00 pc
Blind Rivets 752.00 pc
Consumables (3% of Materials Cost) 1.00 lot

Labor
1 Foreman 1.00 days
1 Skilled Laborer 1.00 days
1 Laborer 1.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1016(1)a Waterproofing (Cement-base)
Quantity 118.00 sq.m

Materials
Waterproofing (Cement-based) 124.00 sq.m
Consumables (3% of Materials Cost) 1.00 lot

Labor
1 Foreman 8.00 days
1 Skilled Laborer 8.00 days
1 Laborer 8.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(8) Sewer Line Works
Quantity 1.00 l.s.

Materials
100 mm uPVC Pipe (3m) 16.00 pcs
50 mm PVC Pipe (3m) 11.00 pcs
PVC 87.5 deg. Single Branch, Seep Tee (101 mm x 50 mm) 8.00 pcs
PVC 87.5deg. (6mm BEND x 101mm) 9.00 pcs
PVC Seep, Tee, Single Branch, 87.5° (101mm x 101mm) 17.00 pcs
PVS Solvent Cement 20.00 liter
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 4.00 days
1 Skilled Laborer 4.00 days
2 Laborer 4.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(24) Cold Water lines
Quantity 1.00 l.s.

Materials
PPR Pipe (32mm dia) 8.00 pcs
PPR Coupling Elbow (32 mm dia) 10.00 pcs
PPR Tee Banded (32 mm dia) 16.00 pcs
Teflon Tape 216.00 roll
Gate Valve (32 mm) 4.00 pcs
Check Valve (32 mm) 1.00 pcs
Water Meter (32 mm) 1.00 pcs
Stainless Steel Water Storage Tank (3000L) 1.00 pcs
1 HP Automatic Water Pump 1.00 pcs
Consumables (5% of Materials) 1.00 lot

Labor
1 Foreman 7.00 days
2 Skilled Laborer 7.00 days
3 Laborer 7.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1002(4) Plumbing Fixtures
Quantity 1.00 l.s.

Materials
Water Closet inc. fittings & acc - American std or equivalent 7.00 pcs

Lavatory inc. fittings & acc. American std or equivalent 4.00 pcs

Floor Drain 11.00 pcs
Urinal 2.00 pcs
Urinal Drain 2.00 pcs
Faucet 6.00 pcs
Brass Clean-Out 1.00 pcs

Labor
1 Foreman 4.00 days
2 Skilled Laborer 4.00 days
2 Laborer 4.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(9) Storm Drainage and Downspout
Quantity 1.00 l.s.

Materials
PVC PIPES (101mm D) 9.00 pcs
PVC 45deg. SINGLE BRANCH, WYE (101mm x 101mm) 4.00 pcs
Solvent 5.00 liters

Labor
1 Foreman 2.00 days
1 Skilled Laborer 2.00 days
1 Laborer 2.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(11) Septic Vault/ Tank (Concrete / CHB)
Quantity 1.00 l.s.

Materials
Portland Cement 68.00 bags
Sand 5.00 cu.m.
Gravel 6.00 sq.m.
Reinforcing Steel Bar 916.00 kgs
G.I. Wire 26.00 kgs
Lumber, Good - 4 uses 164.00 bd-ft
Marine Plywood (1/2"x4"x8') 13.00 pc
Assorted CWN (1kg/100bd.ft) 4.00 kgs
Water Proofing Cement (Sahara or Equivalent) 13.00 bags
Brass Clean-out 4.00 pc

Labor
1 Foreman 4.00 days
2 Skilled Laborer 4.00 days
4 Laborer 4.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1001(6) Catch Basin
Quantity 1.00 l.s

Materials
Portland Cement 28.00 bags
Sand 7.00 cu.m
Gravel 7.00 cu.m
Grade 40 Steel 273.00 kgs
#16 Galvanized Iron Wire 5.46 kgs
Consumables 1.00 lot

Labor

1 Foreman 3.00 days
2 Skilled Laborer 3.00 days
4 Laborer 3.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1100(10) Conduits, Boxes & Fittings (Conduit Works/Conduit Rough-in)
Quantity 1.00 l.s.

Materials
20 mmØ uPVC conduit 100.00 l.m
20 mmØ PVC Adapter 40.00 l.m
RSC Pipe 1" 1.00 pc
Utility box, deep type 36.00 pc
Junction box, deep type 40.00 pc
Consumables 1.00 lot

Labor
1 Foreman 2.00 days
1 Skilled Laborer 2.00 days
2 Laborer 2.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1101(33) Wires and Wiring Devices
Quantity 1.00 l.s.

Materials
Wires THWN/THHN 5.5 mm2 110.00 l.m.
Wires THWN/THHN 14 mm2 10.00 l.m.
Wires THWN/THHN 8.0 mm2 1.00 box
Wires THWN/THHN 3.5 mm2 2.00 box
Wires THWN/THHN 2.0 mm2 2.00 box
One-gang Switch 8.00 set
One-gang Two Way Switch 2.00 set
Two-Gang Switch 6.00 set
Duplex Convenience Outlet 12.00 set
Special Purpose Outlet 2.00 set
Tape, bolt&nut etc. 1.00 lot
JB cover clamps, screw and anchors 1.00 lot
Split Type Aircon 2 HP 2.00 lot
Exhaust Fan 2.00 lot
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 9.00 days
3 Skilled Laborer 9.00 days
5 Laborer 9.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1102(1) Panelboard with Main & Branch Breakers
Quantity 1.00 l.s.

Materials
Circuit Breaker 2.00 lot
Panelboard Nema 3R 2.00 lot
Weather Tight Connector 1" 2.00 pcs
Grounding Clamp 5/8 1.00 pc
Gronding Rod 5/8 1.00 pc
Secondary Rack Single Spool 1.00 pc
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 6.00 days
2 Skilled Laborer 6.00 days
2 Laborer 6.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1103(1) Lighting Fixtures
Quantity 1.00 l.s.

Materials
12 watts Recessed Ceiling-mounted LED Box-type light 19.00 set
T8 18w Louver Type Double Tube Fluorescent Daylight 16.00 set
Emergency Light 12V Dual Light and Color 6.00 unit
Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 5.00 days
2 Skilled Laborer 5.00 days
2 Laborer 5.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1201 (9) a Overhead Tank (Stainless)
Quantity 1.00 set

Materials
PVC Pipe, 75mm dia. X 3m, S-1000 4.00 pc
PVC Blue Pipe, 50mm dia. X 3m 3.00 pc

PVC Blue Pipe, 20mm dia. X 3m 1.00 pc
PVC Elbow, 75mm dia. X 90deg bend 12.00 pc
PVC Elbow, 75mm dia. X 45deg bend 8.00 pc
PVC Blue Elbow, 20mm dia. X 90deg bend 2.00 pc
PVC Blue Elbow, 50mm dia. X 90deg bend 2.00 pc
PVC Blue Tee, 50mm dia. 1.00 pc
Stainless coupling 304, 50mm dia 3.00 pc
Stainless coupling 304, 20mm dia 2.00 pc
PVC Reducer Coupling, 75mm dia X 50mm dia 1.00 pc
Gate Valve, 50mm dia 1.00 pc
Hose Bibb, 20mm dia 1.00 pc
PVC Solvent, 200cc 3.00 pc
Stainless Steel Tank (304), 1.90 x 3.0 m (Vertical), includes platform ladder 1.00 pc

Consumables 1.00 lot

Labor
1 Foreman 8.00 days
2 Skilled Laborer 8.00 days
2 Laborer 8.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1102(18) Solar Panel with Inverter, Battery and Other Devices
Quantity 1.00 l.s.

Materials
Hydbrid Inverter - 12KW 1.00 pc
15kWhigh Voltage LiFePo4 Battery 2.00 pc
Smart Meter 1PH - LHE12DRR11001 1.00 pc
GCL Solar Panel 620W NT12R/66GDF 20.00 pc
MA Rail L2400 22.00 pc
MA Mid Clamp 35mm 44.00 pc
MA End Clamp 35mm 60.00 pc
MA Ground Clamp 35mm 22.00 pc
MA Lfoot 60.00 pc
MA Splicer 44.00 pc
PV Wire Twin Core 2*6mm 200.00 meter
AC Wire THHN 30 mm2 60.00 meter
AC Wire THHN 3.5 mm2 100.00 meter
PV Connector MC4-6mm 12.00 pc
DC MCB-63 2P 600V 20A 6.00 pc
DC Surge Protection Device 2P 600V 20-40 Kpa 6.00 pc
AC Surge Protection Device 2P 275V 20-40 Kpa 1.00 pc
ATS (SQ3M-125/2 230V400V) 125A 2P 1.00 pc
DC Combiner Box 225A with Joymell MCCB 1.00 pc
AC MCB (SCB8-63 400V)2P 100A 2.00 pc
Flexible HDPE "1" 40mm 200.00 meter
Metal Enclosure Box (800*600*200) 1.00 pc
Metal Ground Rod 3M 1.00 pc
Cable tray Slotted 80x80 mm 4.00 pc
Consumables and other hardwares 1.00 lot

Labor
1 Foreman 12.00 days
10 Skilled Laborer 12.00 days
10 Laborer 12.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1106(1) CCTV System
Quantity 1.00 l.s.

Materials
4mp Full Color Camera 12.00 units
16CH NVR 1.00 pc
8TB Surveillance HDD 1.00 pc
24-Port Gigabit PoE Switch 1.00 pc
1500VA UPS 1.00 pc
43" 4K Smart TV/Monitor 1.00 pc
CAT6 UTP Cable 6.00 boxes
CCTV Cabinet, Patch Panel, Connectors, Junction Boxes, RJ45, Mounts & Accessories
1.00 lot

Labor
1 Foreman 5.00 days
2 Skilled Laborer 5.00 days
2 Laborer 5.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1202(6)a1 Fire Extinguisher (10 lbs ABC Dry Chemical)
Quantity 6.00 set

Materials
10 lbs Fire Extinguisher (ABC Dry Chemical with Wall Bracket) 4.00 set(s)

Consumables (5% of Materials Cost) 1.00 lot

Labor
1 Foreman 3.00 days
1 Skilled Laborer 3.00 days
1 Laborer 3.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

1208(1) Fire Alarm System
Quantity 1.00 L.s.

Materials
Fire Alarm Control Panel 1.00 set
Manual Pull Switch 2.00 set
Bell, Vibrating Type 2.00 set
Equipment for Fire Alarm, Smoke Detector 4.00 pcs
Consumables 1.00 lot

Labor
1 Foreman 4.00 days
1 Skilled Laborer 4.00 days
1 Laborer 4.00 days

Equipment
1 Minor Tools (10% of Labor Cost) 1.00 lot

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Construction of Two-Storey School Building	San Isidro Elementary School, Brgy. San Isidro, Tiaong, Quezon	1	Lot	9,993,072.69

Pre-bid Conference

Date	Time	Venue
22/10/2026	3:00:00 PM	Office of the Bids and Awards Committee

Other Information
NOTE:

1. In case of discrepancy between the posted ITB and the Purchase Request (uploaded in associated components), the Purchase Request (PR) will prevail.

2. Interested bidders are advised to purchase the bidding documents no later than one (1) day before the scheduled opening of bids.

REMINDER:
In case interested bidders are unable to access the Associated Components (containing checklist, PR, POW, project plan & sample pictures), please notify the Secretariat immediately. Upon notification, the Secretariat will provide you with a hard copy of the documents upon purchase of the bid documents.

PREPARATION OF DOCUMENTS
1. Bidders are required to submit two (2) copies (Original & Duplicate) of each set (Class “A” & Class “B”) of documents in separate envelopes: Class “A” documents, containing the legal, technical & financial documents; and Class “B” documents containing the financial proposal (including original copy of duly signed and accomplished Bid Form and bid price/bill of quantities).

2. Envelopes must be addressed to the BAC Chairman with proper label indicating the name of project, ABC & name of bidder. The envelopes must be signed and sealed properly.

3. Technical Documents must be ring bound with appropriate tabs.

4. Provide LETTER OF INTENT (2 copies) upon purchase of bidding documents; or include as the first page of the Class "A" documents.

Created by	Noreen A. Ortega
Date Created	14/10/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.

© 2004-2026 DBM Procurement Service. All rights reserved.